

EARTHWORK SCHEDULE I-64

ALIGNMENT	STATION	TO	STATION	EARTH EXCAVATION			
				CU YD	*EARTH EXCAVATION ADJUSTED FOR SHRINKAGE ¹	*EMBANKMENT ²	*EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) ³
RAMP 64W55N-B	59+50.00	TO	60+00.00	2,988	2,241	4	+2,237
	60+00.00	TO	60+50.00	2,042	1,532	1	+1,531
	60+50.00	TO	61+00.00	1,632	1,224	0	+1,224
	61+00.00	TO	61+50.00	1,492	1,119	0	+1,119
	61+50.00	TO	62+00.00	1,008	756	328	+428
	62+00.00	TO	62+50.00	980	735	561	+174
	62+50.00	TO	63+00.00	1,444	1,083	375	+708
	63+00.00	TO	63+50.00	1,835	1,377	253	+1,124
	63+50.00	TO	64+00.00	1,947	1,461	197	+1,264
	64+00.00	TO	64+38.91	1,398	1,049	153	+896
RAMP 64W55N-B SUBTOTAL				16,766	12,577	1,872	+10,705

ALIGNMENT	STATION	TO	STATION	EARTH EXCAVATION			
				CU YD	*EARTH EXCAVATION ADJUSTED FOR SHRINKAGE ¹	*EMBANKMENT ²	*EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) ³
RAMP 64W55S	123+64.87	TO	123+84.47	1	1	0	+1
	123+84.47	TO	124+00.00	2	2	0	+2
	124+00.00	TO	124+50.00	10	8	0	+8
	124+50.00	TO	125+00.00	12	9	0	+9
	125+00.00	TO	125+50.00	12	9	0	+9
	125+50.00	TO	126+00.00	11	9	0	+9
	126+00.00	TO	126+50.00	12	9	0	+9
	126+50.00	TO	127+00.00	16	12	0	+12
	127+00.00	TO	127+50.00	18	14	0	+14
	127+50.00	TO	127+85.71	13	10	0	+10
	127+85.71	TO	128+00.00	6	5	0	+5
	128+00.00	TO	128+50.00	18	14	0	+14
	128+50.00	TO	129+00.00	13	10	0	+10
	129+00.00	TO	129+50.00	10	8	0	+8
	129+50.00	TO	130+00.00	9	7	0	+7
	130+00.00	TO	130+50.00	8	6	0	+6
	130+50.00	TO	131+00.00	6	5	0	+5
	131+00.00	TO	131+50.25	3	3	0	+3
	131+50.25	TO	132+45.66	2	2	0	+2
	132+45.66	TO	132+50.00	0	0	0	0
132+50.00	TO	133+00.00	5	4	0	+4	
133+00.00	TO	133+50.00	10	8	0	+8	
133+50.00	TO	133+75.15	5	4	0	+4	
RAMP 64W55S SUBTOTAL				202	159	0	+159

ALIGNMENT	STATION	TO	STATION	EARTH EXCAVATION			
				CU YD	*EARTH EXCAVATION ADJUSTED FOR SHRINKAGE ¹	*EMBANKMENT ²	*EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) ³
RAMP 55N64E	61+96.34	TO	62+01.75	13	10	0	+10
	62+01.75	TO	62+50.00	123	93	0	+93
	62+50.00	TO	63+00.00	161	121	0	+121
	63+00.00	TO	63+50.00	158	119	1	+118
	63+50.00	TO	64+00.00	132	99	3	+96
	64+00.00	TO	64+50.00	120	90	2	+88
	64+50.00	TO	65+00.00	145	109	0	+109
	65+00.00	TO	65+50.00	183	138	1	+137
	65+50.00	TO	66+00.00	195	147	1	+146
	66+00.00	TO	66+50.00	212	159	0	+159
	66+50.00	TO	67+00.00	269	202	6	+196
	67+00.00	TO	67+50.00	331	249	6	+243
	67+50.00	TO	68+00.00	320	240	12	+228
	68+00.00	TO	68+20.99	159	120	18	+102
	68+20.99	TO	68+50.00	359	270	77	+193
	68+50.00	TO	69+00.00	788	591	188	+403
	69+00.00	TO	69+04.48	73	55	16	+39
	69+04.48	TO	69+50.00	711	534	84	+450
	69+50.00	TO	70+00.00	1,097	823	11	+812
	70+00.00	TO	70+48.49	1,610	1,208	0	+1,208
70+48.49	TO	71+00.00	1,840	1,380	0	+1,380	
71+00.00	TO	71+50.00	1,349	1,012	0	+1,012	
71+50.00	TO	71+66.13	270	203	0	+203	
RAMP 55N64E SUBTOTAL				10,618	7,972	426	+7,546

EARTHWORK SCHEDULE I-64 (CONT.)

ALIGNMENT	STATION	TO	STATION	EARTH EXCAVATION			
				CU YD	*EARTH EXCAVATION ADJUSTED FOR SHRINKAGE ¹	*EMBANKMENT ²	*EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) ³
RAMP 64W70W	60+98.81	TO	61+50.00	2,748	2,061	0	+2,061
	61+50.00	TO	62+00.00	3,228	2,421	0	+2,421
	62+00.00	TO	62+50.00	3,686	2,765	0	+2,765
	62+50.00	TO	63+00.00	239	180	0	+180
	63+00.00	TO	63+50.00	214	161	23	+138
	63+50.00	TO	64+00.00	187	141	183	-42
	64+00.00	TO	64+50.00	160	120	255	-135
	64+50.00	TO	64+87.96	114	86	174	-88
	64+87.96	TO	65+00.00	25	19	33	-14
	65+00.00	TO	65+34.90	43	33	0	+33
RAMP 64W70W SUBTOTAL				10,644	7,987	668	+7,319

ALIGNMENT	STATION	TO	STATION	EARTH EXCAVATION			
				CU YD	*EARTH EXCAVATION ADJUSTED FOR SHRINKAGE ¹	*EMBANKMENT ²	*EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) ³
I-64 EB	26+70.53	TO	27+00.00	826	620	0	+620
	27+00.00	TO	27+25.00	434	326	0	+326
	27+25.00	TO	27+66.46	594	446	0	+446
	27+66.46	TO	28+00.00	435	327	1	+326
	28+00.00	TO	28+50.00	643	483	1	+482
	28+50.00	TO	29+00.00	684	513	0	+513
	29+00.00	TO	29+34.72	463	348	1	+347
	29+34.72	TO	29+50.00	212	159	1	+158
	29+50.00	TO	30+00.00	741	556	0	+556
	30+00.00	TO	30+38.69	514	386	0	+386
	30+38.69	TO	30+50.00	132	99	0	+99
	30+50.00	TO	31+00.00	555	417	0	+417
	31+00.00	TO	31+50.00	501	376	0	+376
	31+50.00	TO	32+00.00	438	329	0	+329
	32+00.00	TO	32+50.00	403	303	0	+303
	32+50.00	TO	32+72.72	175	132	0	+132
	32+72.72	TO	33+00.00	243	183	0	+183
	33+00.00	TO	33+37.91	326	245	0	+245
	33+37.91	TO	33+50.00	84	63	0	+63
	33+50.00	TO	34+00.00	338	254	3	+251
	34+00.00	TO	34+50.00	335	252	8	+244
	34+50.00	TO	34+75.27	168	126	8	+118
	34+75.27	TO	35+00.00	164	123	13	+110
	35+00.00	TO	35+13.41	90	68	8	+60
	35+13.41	TO	35+50.00	243	183	24	+159
	35+50.00	TO	36+00.00	308	231	18	+213
	36+00.00	TO	36+50.00	290	218	0	+218
	36+50.00	TO	36+90.46	234	176	0	+176
	36+90.46	TO	37+00.00	55	42	0	+42
	37+00.00	TO	37+50.00	300	225	0	+225
	37+50.00	TO	38+00.00	308	231	0	+231
	38+00.00	TO	38+50.00	294	221	1	+220
	38+50.00	TO	39+00.00	276	207	3	+204
	39+00.00	TO	39+50.00	282	212	37	+175
	39+50.00	TO	39+75.98	171	129	22	+107
	39+75.98	TO	40+00.00	189	142	4	+138
	40+00.00	TO	40+50.00	425	319	5	+314
	40+50.00	TO	40+85.82	306	230	7	+223
	40+85.82	TO	41+00.00	122	92	2	+90
	41+00.00	TO	41+50.00	379	285	1	+284
41+50.00	TO	42+00.00	320	240	11	+229	
42+00.00	TO	42+50.00	291	219	14	+205	
42+50.00	TO	43+00.00	289	217	6	+211	
43+00.00	TO	43+32.90	213	160	2	+158	
43+32.90	TO	43+50.00	108	81	5	+76	
43+50.00	TO	44+00.00	277	208	13	+195	
44+00.00	TO	44+50.00	308	231	4	+227	
44+50.00	TO	45+00.00	342	257	5	+252	
45+00.00	TO	45+50.00	347	261	2	+259	
45+50.00	TO	45+92.22	208	156	0	+156	
45+92.22	TO	46+00.00	21	16	0	+16	

EARTHWORK SCHEDULE I-64 (CONT.)

ALIGNMENT	STATION	TO	STATION	EARTH EXCAVATION				
				CU YD	*EARTH EXCAVATION ADJUSTED FOR SHRINKAGE ¹	*EMBANKMENT ²	*EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) ³	
I-64 EB	46+00.00	TO	46+50.00	127	96	0	+96	
	46+50.00	TO	46+71.34	54	41	0	+41	
	46+71.34	TO	47+00.00	74	56	0	+56	
	47+00.00	TO	47+50.00	129	97	0	+97	
	47+50.00	TO	47+84.68	90	68	0	+68	
	47+84.68	TO	48+00.00	27	21	1	+20	
	48+00.00	TO	48+50.00	23	18	1	+17	
	48+50.00	TO	49+00.00	0	0	0	0	
	49+00.00	TO	49+50.00	1	1	5	-4	
	49+50.00	TO	50+00.00	3	3	7	-4	
	50+00.00	TO	50+50.00	21	16	2	+14	
	50+50.00	TO	50+75.75	20	15	0	+15	
	50+75.75	TO	51+00.00	19	15	0	+15	
	51+00.00	TO	51+50.00	38	29	0	+29	
	51+50.00	TO	52+00.00	39	30	0	+30	
	52+00.00	TO	52+50.00	41	31	0	+31	
	52+50.00	TO	53+00.00	44	33	0	+33	
	53+00.00	TO	53+50.00	49	37	0	+37	
	53+50.00	TO	54+00.00	50	38	0	+38	
	54+00.00	TO	54+50.00	51	39	0	+39	
	54+50.00	TO	55+00.00	53	40	0	+40	
	55+00.00	TO	55+50.00	52	39	0	+39	
	55+50.00	TO	56+00.00	52	39	0	+39	
	56+00.00	TO	56+50.00	58	44	1	+43	
	56+50.00	TO	57+00.00	65	49	3	+46	
	57+00.00	TO	57+50.00	71	54	5	+49	
	57+50.00	TO	58+00.00	70	53	6	+47	
	58+00.00	TO	58+50.00	66	50	12	+38	
	58+50.00	TO	59+00.00	64	48	11	+37	
	59+00.00	TO	59+50.00	65	49	3	+46	
	59+50.00	TO	60+00.00	75	57	1	+56	
	60+00.00	TO	60+49.65	43	33	0	+33	
	I-64 MAINLINE SUB TOTALS				18,038	13,562	288	+13,274

LOCATION SUMMARY				
RAMP 64W55S SUBTOTAL	202	159	0	+159
RAMP 55N64E SUBTOTAL	10,618	7,972	426	+7,546
RAMP 64W70W SUBTOTAL	10,644	7,987	668	+7,319
I-64 MAINLINE SUB TOTALS	18,038	13,562	288	+13,274
RAMP 64W55N-B SUBTOTAL	16,766	12,577	1,872	+10,705

I-64 SUB-TOTAL	56,268	42,257	3,254	+39,003
ROUNDED TOTAL⁴	56,270			