

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE 0014		
20200500	EARTH EXCAVATION (WIDENING)	CU YD	10	10		
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	178	178		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.1	0.1		
40600300	AGGREGATE (PRIME COAT)	TON	1	1		
40600990	TEMPORARY RAMP	SQ YD	95	95		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	86	86		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1095	1095		
44004250	PAVED SHOULDER REMOVAL	SQ YD	178	178		
50102400	CONCRETE REMOVAL	CU YD	14	14		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	15.5	15.5		
50300300	PROTECTIVE COAT	SQ YD	191	191		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2400	2400		
50800515	BAR SPLICERS	EACH	32	32		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE 0014		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	89	89		
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	852	852		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	562.5	562.5		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	562.5	562.5		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2378	2378		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10	10		

\* SPECIALTY ITEM

FILE NAME =	USER NAME = gelinh	DESIGNED -	REVISED -
e:\p\work\p\idos\gelinh\d0266267\0876F07-at-plan.dgn		DRAWN -	REVISED -
PLOT SCALE = 1/8" = 1' / in.		CHECKED -	REVISED -
PLOT DATE = 2/7/2012		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: \_\_\_\_\_ SHEET NO. \_\_\_\_\_ OF \_\_\_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
861	110BR-1	RANDOLPH	14	3
CONTRACT NO. 76F07				
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				