

SUMMARY OF EARTHWORK					
LOCATION	20200100				
	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT, ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	WASTE (BORROW)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD (1)	CU YD
STA 1370+50 TO 1372+73	42.6	32.0	50.9	(18.95)	-18.95
STA 1373+73 TO 13766+50	68.5	51.4	70.4	(19.03)	-37.98
TOTAL	111	83	121	(38)	-38

NOTES:
1- NO PAYMENT WILL BE ALLOWED FOR OVERHAUL
2- BORROW MATERIAL SHALL BE FURNISHED FROM THE STRUCTURE EXCAVATION (50200100)

APPROACH SLAB REMOVAL SCHEDULE			
APPROXIMATE STATION	WIDTH	APPROXIMATE LOCATION	Z0004552
			APPROACH SLAB REMOVAL
	FT		SQ. YD
1372+55.57 to 1372+75.57	24	EX SN 076-0026	53.33
1373+76.49 to 1373+96.49	24	EX SN 076-0026	53.33
TOTAL			107

PAVEMENT REMOVAL SCHEDULE		
APPROXIMATE STATION	WIDTH	44000100
		PAVEMENT REMOVAL
	FT	SQ. YD
1372+42.50 TO 1372+55.57	24	34.85
1373+96.49 TO 1374+09.50	24	34.69
TOTAL		70

PAVED SHOULDER REMOVAL SCHEDULE		
APPROXIMATE STATION	WIDTH	44004250
		PAVED SHOULDER REMOVAL
	FT	SQ. YD
RT STA 1371+34.00 TO STA 1372+75.57	3.042	47.84
RT STA 1373+76.49 TO STA 1375+15.00	3.759	57.85
TOTAL		106

PERIMETER EROSION BARRIER	
LOCATION	28000400
	PERIMETER EROSION BARRIER
	FT
LT SIDE	658
RT SIDE	549
TOTALS	1207

SEEDING SCHEDULE								
STATION TO STATION	25000200	25000350	25000400	25000500	25000600	25000700	25100115	28000250
	SEEDING CLASS 2	SEEDING CLASS 7	NITROGEN FERTILIZER NUTRIENTS	PHOSPHOROUS FERTILIZER NUTRIENTS	POTASSIUM FERTILIZER NUTRIENTS	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2	TEMPORARY EROSION CONTROL SEEDING
	ACRES	ACRES	LBS	LBS	LBS	TON	ACRES	LBS
LT STA 1370+50 TO 1372+50	0.012	0.012	1.6	1.1	1.1	0.02	0.025	1.228
LT STA 1374+00 TO 1376+50	0.008	0.008	1.0	0.7	0.7	0.02	0.016	0.794
RT STA 1370+50 TO 1372+50	0.030	0.030	3.9	2.7	2.7	0.06	0.060	2.977
RT STA 1374+00 TO 1376+50	0.042	0.042	5.4	3.7	3.7	0.08	0.083	4.163
TOTALS	0.25 *	0.25 *	12	8	8	0.2	0.50 *	10

* TOTALS ARE ROUNDED UP TO MINIMUM VALUE SHOWN IN BDE FIG. 64-1A

TEMPORARY CONCRETE BARRIER SCHEDULE		
LOCATION	70400100	70400200
	TEMP CONC BARRIER	TEMP CONC BARRIER, RELOCATE
	FT	FT
STAGE I		
STA 1371+17.32 TO STA 1372+17.00	100	
STA 1372+17.00 TO STA 1374+29.50	212.5	
STA 1374+29.50 TO STA 1375+29.18	100	
STAGE II		
STA 1371+42.34 TO STA 1372+42.00		100
STA 1372+42.00 TO STA 1374+29.50		187.5
STA 1374+29.50 TO STA 1375+29.10		100
TOTALS	412.5	387.5

HMA BASE COURSE WIDENING SCHEDULE	
LOCATION	35600716
	HMA BASE COURSE WIDENING, 10"
	SQ YD
RT STA 1371+34.00 TO STA 1372+73.91	48
RT STA 1373+73.39 TO STA 1375+15.00	87
TOTAL	135

IMPACT ATTENUATORS, TEMPORARY (NON REDIRECTIVE), TEST LEVEL 3		
LOCATION	Z0030250	Z0030350
	IMPACT ATTENUATOR	IMPACT ATTENUATOR, RELOCATE
	EACH	EACH
STAGE I		
STA 1371+17.32	1	
STA 1375+29.18	1	
STAGE II		
STA 1371+42.34		1
STA 1375+29.10		1
TOTALS	2	2

HMA SHOULDER SCHEDULE		
LOCATION (STATION TO STATION)	48203029	48203037
	HMA SHOULDER, 8"	HMA SHOULDER, 10"
	SQ YD	SQ YD
LT STA 1370+50.62 TO STA 1371+34.00	60.5	
LT STA 1371+34.00 TO STA 1372+42.50		75.7
LT STA 1374+09.50 TO STA 1375+15.00		76.1
RT STA 1371+23.63 TO STA 1372+73.91		157.6
LT STA 1375+15.00 TO STA 1376+55.87	105.4	
RT STA 1375+15.00 TO STA 1376+05.61	65.3	
TOTAL	231	309

BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) SCHEDULE		
LOCATION STA TO STA	WIDTH	42001430
		BR APPR PVT CONN (FLEX)
	FT	SQ. YD
1372+42.50 TO 1372+48.50	33	22.5
1374+03.50 TO 1374+09.50	33	22.5
TOTAL		45

