

SUMMARY OF QUANTITIES

LOCATION	RURAL-STP
ROUTE	FAS 855 (IL 14)
FUNDING	20% STATE 80% FED
COUNTY	HAMILTON
CONSTRUCTION TYPE	ROADWAY <i>COMBINE</i>
TYPE CODE	0005 0005

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY		STA 121+15 TO STA 163+12
Z0034105	MATERIAL TRANSFER DEVICE	TON	18,720	16,565	2,155
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13,927	12,381	1,546
40600300	AGGREGATE (PRIME COAT)	TON	226	200	26
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL*4.75, N50	TON	6,277	5,554	723
40600982	HOT-MIX ASPHALT SURFACE REMOVAL • BUTT JOINT	SQ YD	45	45	
40600990	TEMPORARY RAMP	SQ YD	68	45	23
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	12,443	11,011	1,432
40800050	INCIDENTAL HMA SURFACING	TON	383	383	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/4"	SQ YD	14,583		14,583
44000151	HOT-MIX ASPHALT SURFACE REMOVAL 1/2"	SQ YD	132,944	130,500	2,444
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	1,902	1,791	111
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	86	70	16
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	2,521	2,477	44
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3	