

SUMMARY OF QUANTITIES

LOCATION	RURAL-STP	
ROUTE	FAS 855 (IL 14)	
FUNDING	20% STATE 80% FED	
COUNTY	HAMILTON	
CONSTRUCTION TYPE	ROADWAY	
TYPE CODE	0005	0005

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY		STA 121+15 TO STA 163+12
67100100	MOBILIZATION	L SUM	1	0.75	0.25
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.75	0.25
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.75	0.25
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	1	
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	13,932	13,178	754
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	122	122	
70300220	TEMPORARY PAVEMENT MARKING, LINE 4"	FOOT	131,446	127,949	3,497
70300240	TEMPORARY PAVEMENT MARKING • LINE 6"	FOOT	84		84
70300280	TEMPORARY PAVEMENT MARKING • LINE 24"	FOOT	156	72	84
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	44,051	42,843	1,208
* 78000100	THERMOPLASTIC PAVEMENT MARKING • LETTERS AND SYMBOLS	SO FT	122	122	
* 78001110	PAINT PAVEMENT MARKING • LINE 4"	FOOT	134,461	127,949	6,512
* 78001130	PAINT PAVEMENT MARKING • LINE 6"	FOOT	84		84
* 78000650	THERMOPLASTIC PAVEMENT MARKING • LINE 24"	FOOT	156	72	84
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	604	549	55
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	405	363	42

* SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -
ei:\pw\work\puidot\kellgk\d0271238\7827	Design.dgn	DRAWN -	REVISED -
	PLOT SCALE = 400.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 2/2/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
855	(9,10)RS-2	HAMILTON	30	6
CONTRACT NO. 78271			ILLINOIS FED. AID PROJECT	