

SCHEDULE OF QUANTITIES

DATE	BY	REVISIONS	PLOTTED	TEMPLATE	AREAS CHECKED

DATE	BY	REVISIONS	PLOTTED	TEMPLATE	AREAS CHECKED

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT	QUANTITY	UNIT	QUANTITY
20200100	EARTH EXCAVATION	CU YD	48.8	28000400	PERIMETER EROSION BARRIER	FOOT	1509.2
	RT./LT. STA. 601+55 TO 603+32.46		48.8		RT. STA. 69+25 TO 75+65		640.0
					RT. STA. 600+00 TO 601+00		100.0
					LT. STA. 600+75 TO 608+44.18		769.2
	TOTAL		48.8		TOTAL		1509.2
20400800	FURNISHED EXCAVATION	CU YD	319.9	550B0040	STORM SEWERS, CLASS B, TYPE 1, 10"	FOOT	114.0
	RT./LT. STA. 600+00 TO 601+55		114.6		RT./LT. 601+20 TO 601+50 +/-		40.0
	RT./LT. STA. 603+32.46 TO 608+18		254.2		RT./LT. 603+50 TO 603+53 +/-		25.0
					RT./LT. 605+50 TO 605+52 +/-		39.0
	TOTAL		319.9		TOTAL		114.0
20800150	TRENCH BACKFILL	CU YD	6.4	28000500	INLET AND PIPE PROTECTION	EACH	3.0
	RT./LT. 601+20 TO 601+50 +/-		2.9		RT. STA. 601+20		1.0
	RT./LT. 603+50 TO 603+53 +/-		1.8		RT. STA. 603+50		1.0
	RT./LT. 605+50 TO 605+52 +/-		1.8		RT. STA. 605+50		1.0
	TOTAL		6.4		TOTAL		3.0
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	3,894.5	35101400	AGGREGATE BASE COURSE, TYPE B	TON	1,391.8
	RT./LT. STA. 44+50 TO 75+65		2,768.9		RT./LT. STA. 44+53		2.5
	RT./LT. STA. 600+00 TO 608+44.18		1,125.6		RT./LT. STA. 44+73		2.5
					RT./LT. STA. 44+50 TO 75+65		1040.6
					RT./LT. STA. 600+00 TO 608+44.18		346.1
	TOTAL		3,894.5		TOTAL		1,391.8
25000300	SEEDING, CLASS 3	ACRE	1.46	66400105	CHAIN LINK FENCE, 4'	FOOT	1,150.0
	RT./LT. STA. 2+97.13 TO 6+75		0.052		RT. STA. 64+65 TO 75+65		1100.0
	RT./LT. STA. 6+75 TO 44+30		0.517		RT. STA. 600+00 TO 600+50		50.0
	RT./LT. STA. 44+50 TO 75+65		0.429				
	RT./LT. STA. 600+00 TO 608+44.18		0.465		TOTAL		1150.0
	TOTAL		1.46		TOTAL		1150.0
25100115	MULCH, METHOD 2	ACRE	1.46	66400305	CHAIN LINK FENCE, 6'	FOOT	27.0
	RT./LT. STA. 2+97.13 TO 6+75		0.052		LT. STA. 608+20 +/- TO 608+44.18		27.0
	RT./LT. STA. 6+75 TO 44+30		0.517				
	RT./LT. STA. 44+50 TO 75+65		0.429		TOTAL		27.0
	RT./LT. STA. 600+00 TO 608+44.18		0.465				
	TOTAL		1.46		TOTAL		27.0
25100630	EROSION CONTROL BLANKET	SQ YD	2251.1	66401300	CHAIN LINK GATES, 4' X 10' SINGLE	EACH	1.0
	RT./LT. STA. 600+00 TO 608+44.18		2251.1		RT. STA. 600+80 +/-		1.0
					TOTAL		1.0
	TOTAL		2251.1		TOTAL		1.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	439.0	67100100	MOBILIZATION	L SUM	1.0
	RT./LT. STA. 2+97.13 TO 6+75		15.6		PROJECT LIMITS		1.0
	RT./LT. STA. 6+75 TO 44+30		155.2				
	RT./LT. STA. 44+50 TO 75+65		128.7		TOTAL		1.0
	RT./LT. STA. 600+00 TO 608+44.18		139.5				
	TOTAL		439.0		TOTAL		1.0
28000305	TEMPORARY DITCH CHECKS	FOOT	30.0	72000100	SIGN PANEL - TYPE 1	SQ FT	62.5
	RT. STA. 602+00		10.0		LT. STA. 2+70 +/-		6.25
	RT. STA. 604+00		10.0		RT. STA. 8+50 +/-		6.25
	RT. STA. 606+00		10.0		LT. STA. 10+52 +/-		6.25
					LT. STA. 44+40 +/-		4.00
					RT. STA. 44+40 +/-		6.25
					RT. STA. 44+90 +/-		6.25
					RT. STA. 44+90 +/-		6.25
					LT. STA. 44+90 +/-		6.25
					RT. STA. 45+14 +/-		6.25
					LT. STA. 46+12 +/-		6.25
					RT. STA. 52+40 +/-		6.25
					LT. STA. 53+40 +/-		6.25
					RT. STA. 57+64 +/-		6.25
					LT. STA. 59+10 +/-		6.25
					RT. STA. 75+65 +/-		6.25
					RT. STA. 600+72 +/-		3.75
					LT. STA. 601+72 +/-		6.25
					TOTAL		105.50
	TOTAL		30.0		TOTAL		105.50

FILE NAME =	USER NAME =	DESIGNED --	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SCHEDULE OF QUANTITIES		F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -- MPK	REVISED --						10-00043-00-BT	ROCK ISLAND	31	8
		CHECKED -- MKM	REVISED --									
		DATE -- 2.14.12	REVISED --					SCALE:	SHEET NO. 1 OF 1 SHEETS	STA. TO STA.	CONTRACT NO. 85556	
ILLINOIS FED. AID PROJECT												