

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: 0011

PAY CODE	DESCRIPTION	UNIT	QUANTITY
20300100	Channel Excavation	Cu. Yd.	405
25100630	Erosion Control Blanket	Sq. Yd.	1,560
28000250	Temporary Erosion Control Seeding	Pound	32
28000400	Perimeter Erosion Barrier	Foot	671
28100807	Stone Dumped Riprap, Class A4	Ton	1,129
*35101400	Aggregate Base Course, Type B	Ton	435
*40200800	Aggregate Surface Course, Type B	Ton	124
*40600100	Bituminous Materials (Prime Coat)	Gallon	318
*40800050	Incidental Hot-Mix Asphalt Surfacing	Ton	106
*48101200	Aggregate Shoulders, Type B	Ton	29
*50100100	Removal of Existing Structures	Each	1
50200100	Structure Excavation	Cu. Yd.	206
50300225	Concrete Structures	Cu. Yd.	87.0
50300260	Bridge Deck Grooving	Sq. Yd.	527
50300300	Protective Coat	Sq. Yd.	568
*50400505	Precast Prestressed Concrete Deck Beams (27" Depth)	Sq. Ft.	2,870
*50400605	Precast Prestressed Concrete Deck Beams (33" Depth)	Sq. Ft.	2,184
50800205	Reinforcement Bars, Epoxy Coated	Pound	18,240
Δ 50901050	Steel Railing, Type SM	Foot	365
51200958	Furnishing Metal Shell Piles 14"x0.250"	Foot	315
51200959	Furnishing Metal Shell Piles 14"x0.312"	Foot	470
51202305	Driving Piles	Foot	785
51203200	Test Pile Metal Shells	Each	4
51500100	Name Plates	Each	1
67100100	Mobilization	L. Sum	1
72500300	Object Marker - Type 3	Each	4
72900100	Metal Post - Type A	Foot	44
Z0013798	Construction Layout	L. Sum	1
*X2020410	Earth Excavation (Special)	Cu. Yd.	317
*X2070302	Porous Granular Embankment, Special	Ton	310
*X2501000	Seeding, Class 2 (Special)	Acre	0.32
*X5030305	Concrete Wearing Surface, 5"	Sq. Yd.	568
*X7010216	Traffic Control and Protection, (Special)	L. Sum	1

*See the contract documents for Special Provisions.

Δ Specialty Items

FILE: S:\PROJECTS\2011\1224011.Lee.Co.DESIGN\STRUCT\00-quantity\SummofQuantities.dgn



DESIGNED - BRADLEY KLEINMAIER	REVISED -
CHECKED - MEGAN CACKLEY	REVISED -
DRAWN - RON ALLEN	REVISED -
CHECKED - MICHAEL WAGNER	REVISED -

LEE COUNTY
C.H. 12 (KEIGWIN ROAD) OVER GREEN RIVER
STATION 20+00

SUMMARY OF QUANTITIES
STRUCTURE NO. 052-3416

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1180	11-00318-00-BR	LEE	29	2
WHA# 1224D11		CONTRACT NO. 85557		
ILLINOIS FED. AID PROJECT BRS-1180(003)				