



NOTE: THE TRAFFIC SIGNAL POST, BASE, AND STEEL SCREW-IN FOUNDATION WILL BE PAID FOR UNDER TRAFFIC SIGNAL POST AND LIGHT POLE FOUNDATION PAY ITEMS.

RADAR SPEED LIMIT SIGN ASSEMBLY DETAIL

CONSTRUCTION NOTES:

1. THE LOCATION OF ALL UTILITIES AND PRIVATELY OWNED FACILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO THE INSTALLATION OF ANY COMPONENTS.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING EXISTING IDOT ELECTRICAL FACILITIES AT HIS/HER OWN EXPENSE IF REQUIRED, PRIOR TO PERFORMING ANY WORK THE CONTRACTOR SHALL ALSO BE LIABLE FOR ANY DAMAGE TO IDOT FACILITIES RESULTING FROM INACCURATE LOCATING.
3. THE RADAR SPEED LIMIT SIGNS AND ALL ASSOCIATED COMPONENTS SHALL BE IN FULL COMPLIANCE WITH THE LATEST PUBLISHED EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
4. THE RADAR SPEED LIMIT SIGNS SHALL BE INSTALLED AT LOCATIONS AS SPECIFIED BY THE ENGINEER. THE CONTRACTOR SHALL NOTIFY JEREMY PALM, AT (815) 822-0335 FOR LOCATION VERIFICATION PRIOR TO INSTALLATION.
5. THE RADAR SPEED SIGN ASSEMBLIES SHALL BE INSTALLED AT A MINIMUM DISTANCE OF EIGHT FEET FROM THE EDGE OF PAVEMENT.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORATION OF ALL AREAS DISTURBED BY CONSTRUCTION. THE COST OF THIS WORK SHALL BE INCLUDED IN THE BID PRICE FOR THE CONTRACT.
7. THE CONTRACTOR SHALL REMOVE THE EXISTING SPEED LIMIT SIGNS AND POSTS (AS NECESSARY) BETWEEN STATION 102+91.51 AND 106+41.51 AND DELIVER THEM TO THE CITY OF STREATOR. THE CONTRACTOR SHALL NOTIFY JEREMY PALM AT (815) 822-0335, FORTY EIGHT HOURS PRIOR TO DELIVERY.

SUMMARY OF QUANTITIES			
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QTY.
72000200	SIGN PANEL - TYPE 2	SQ FT	15.25
72900100	METAL POST - TYPE A	FOOT	26.5
83600350	LIGHT POLE FOUNDATION, METAL, 11" BOLT CIRCLE, 8"X6"	EACH	1
87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	1
X0326852	RADAR SPEED SIGN	EACH	1

