

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE	
S.I.	S.P.	CODE NO.	PAY ITEM	UNIT	QUAN	0021
		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	20	20
		20800150	TRENCH BACKFILL	CU YD	2	2
		42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	24781	24781
		42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	1599	1599
		42400800	DETECTABLE WARNINGS	SQ FT	488	488
		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	419	419
		44000300	CURB REMOVAL	FOOT	646	646
		44000600	SIDEWALK REMOVAL	SQ FT	8145	7958
		54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2
		542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	14	14
		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	653	653
		67100100	MOBILIZATION	L SUM	1	1
		72000100	SIGN PANEL - TYPE 1	SQ FT	99	99
△		78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	1917	1466
△		78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	388	388
△		78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	226	226
△	*	X0326899	SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	9	9
	*	X2020410	EARTH EXCAVATION (SPECIAL)	CU YD	532	529
	*	X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1
	*	XX006425	RESTORATION	SQ YD	1718	1713
	*	Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	210	210
	*	Z0077700	WOOD FENCE TO BE REMOVED AND RE-ERECTED	FOOT	60	60

* INDICATES SPECIAL PROVISION

△ INDICATES SPECIALTY ITEM

FILE NAME = 10220-QUAN-01 - SUM-1	USER NAME =	DESIGNED -- BDB	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SAFE ROUTES TO SCHOOLS CITY OF PLANO SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	CHECKED -- JRA	REVISED --	VAR			10-00038-00-SW	KENDALL	12	2	
	PLOT SCALE =	DRAWN -- JJB	REVISED --			CONTRACT NO. 87456				
	PLOT DATE = 8/17/2011	CHECKED -- BDB	REVISED --			SCALE:	SHEET NO. 2 OF 12 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT. SRTS-4009(103)	