

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	10-00010-00-SW	DEKALB	11	3
CONTRACT NO. 87457				

SUMMARY OF QUANTITIES

PAY ITEM	PAY ITEM DESCRIPTION	UNIT	[002] QUANTITY
20101200	TREE ROOT PRUNING	EACH	1
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	2
20200100	EARTH EXCAVATION	CU YD	538
20800150	TRENCH BACKFILL	CU YD	84
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3775
21400100	GRADING AND SHAPING DITCHES	FOOT	830
25000100	SEEDING, CLASS 1	ACRE	0.8
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	72
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	72
25100630	EROSION CONTROL BLANKET	SQ YD	3775
28000500	INLET AND PIPE PROTECTION	EACH	13
35101400	AGGREGATE BASE COURSE TYPE B	TON	504
35800100	PREPARATION OF BASE	SQ YD	990
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	4.5
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	495
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	4
40603305	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30	TON	115
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	12
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	15691
42400800	DETECTABLE WARNINGS	SQ FT	220
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	255
44000600	SIDEWALK REMOVAL	SQ FT	467
44002208	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2"	SQ YD	33
44201694	CLASS D PATCHES, TYPE III, 4 INCH	SQ YD	27
50105220	PIPE CULVERT REMOVAL	FOOT	212
542C0217	PIPE CULVERTS, CLASS C, TYPE 1, 12"	FOOT	351
54215547	METAL END SECTIONS 12"	EACH	19
54215550	METAL END SECTIONS 15"	EACH	1
54215553	METAL END SECTIONS 18"	EACH	1
* Δ 56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	1
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
72000100	SIGN PANEL - TYPE 1	SQ FT	44
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	60
Δ 78000400	THERMOPLASTIC PAVEMENT MARKINGS - LINE 6"	FOOT	658
* Z0004510	HMA DRIVEWAY PAVEMENT, 3"	SQ YD	245

* SEE SPECIAL PROVISIONS
Δ SPECIALTY ITEMS

Plotted: February 9, 2012 @ 7:45 AM By: Kie Pung - Tab: 03 Quantities - 22334

COPYRIGHT © 2012 ENGINEERING ENTERPRISES, INC.

Engineering Enterprises, Inc.
CONSULTING ENGINEERS
52 Wheeler Road
Sugar Grove, Illinois 60554
630.466.6700 / www.eeiweb.com

VILLAGE OF HINCKLEY
DEKALB COUNTY, ILLINOIS

1	2/1/12	REVISED PER IDOT COMMENTS FROM 12/14/11
NO.	DATE	REVISIONS

**SAFE ROUTES TO SCHOOL
IMPROVEMENTS**

SUMMARY OF QUANTITIES

DATE:	NOVEMBER 2011
PROJECT NO:	H10804
FILE:	H10804-CVR
SHEET	3 OF 11

Path: \\SBSRFR01\H10804\DWG\DWG_FINAL_ENG\H10804-CVR