

MAINLINE SCHEDULE										
LOCATION	DESCRIPTION	LENGTH	AREA	HMA SURF REM 2 1/4"	POLY, HMA SURF CSE	POLY, LEVEL BINDER (MM)	POLY, LEVEL BINDER (HM)	TEMP RAMP	POLY, BIT MATL (PR CT)	AGG (PR CT)
STA.		FOOT	SQ YD	SQ YD	TON	TON	TON	SQ YD	GALLON	TON
127+25 TO 130+45.76	US 45/52 SOUTH	321	2211.3	2211	186	93	1.1	34.4	287.5	4.4
130+45.76 TO 134+00	US 45/52 NORTH	354	2438.7	2439	205	102	1.2	34.4	317.0	4.9
8+53 TO 9+68.54	JOHN CASEY WEST	116	438.2	438	37	18	0.2	18.9	57.0	0.9
20+30.4 TO 21+56	JOHN CASEY EAST	126	868	868	73	37	0.4	34.4	112.8	1.7
JOHN CASEY DR. SUBTOTALS				5956	501	250	2.9	122.0	774.3	11.9

SIDEWALK SCHEDULE						
LOCATION	DESCRIPTION	SIDEWALK REMOVAL	PCC SIDEWALK 4"	COMB C&G REM	COMBINATION CC&G, TYPE B 6.24	DETECTABLE WARNINGS
		SQ FT	SQ FT	FT	FT	SQ FT
JOHN CASEY DR./ US 45/52	NE QUADRANT	141	124	35	35	8
	SE QUADRANT	85	142	48	48	16
	SW QUADRANT	195	223	50	50	16
	NW QUADRANT	278	303	59	59	16
TOTALS		699	792	192	192	56

PAVEMENT MARKING													
LOCATION	DESCRIPTION	LENGTH FOOT	WORK ZONE PAVT' MK REMOVAL SQ FT	SHORT TERM PAVEMENT MARKING		THERMOPLASTIC PAVEMENT MARKING LINE						LETTERS & SYMBOLS WHITE SQ FT	
				WHITE	YELLOW	4 INCH	6 INCH		8 INCH	12 INCH	24 INCH		
				FOOT	FOOT	FOOT	WHITE	YELLOW	WHITE	WHITE	WHITE		
127+25 TO 130+46.07	US 45/52 SOUTH	321	632	597	106	398	132			216	132	38	46.8
130+46.07 TO 134+00	US 45/52 NORTH	354	958	907	154	623	146	40		211	146	38	78
8+53	JOHN CASEY WEST	131	331	318	38	200	99			100	99	25	31.2
21+56	JOHN CASEY EAST	120	609	596	39	202	139			202	139	41	62.4
TOTALS			2530	2418	337	1423	516	40		729	516	142	218.4

TEMPORARY PAVEMENT MARKING											
LOCATION	DESCRIPTION	LENGTH FOOT	TEMPORARY PAVEMENT MARKING LINE								LETTERS & SYMBOLS SQ FT
			4 INCH	6 INCH		8 INCH	12 INCH	24 INCH			
			YELLOW	WHITE	YELLOW	WHITE	WHITE	WHITE			
127+25 TO 130+46.07	US 45/52 SOUTH	321	398	132			216	132	38	46.8	
130+46.07 TO 134+00	US 45/52 NORTH	354	623	146	40		211	146	38	78	
8+53 TO 9+54	JOHN CASEY WEST	131	200	99			100	99	25	31.2	
20+55 TO 21+56	JOHN CASEY EAST	120	202	139			202	139	41	62.4	
TOTALS			1423	516	40		729	516	142	218.4	

MANHOLE SCHEDULE		
LOCATION	OFFSET	MANHOLE TO BE ADJUSTED
STA	LT/RT	EACH
130+68	52' LT	1
129+87	42' RT	1
TOTAL		2

RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	ONE-WAY CRYSTAL
US 45/52 SOUTH	12
US 45/52 NORTH	16
TOTALS	28

WATER VALVE SCHEDULE		
LOCATION	OFFSET	WATER VALVE TO BE ADJUSTED
STA	LT/RT	EACH
130+67	52.5' LT	1
130+84	56.6' RT	1
TOTAL		2