

SUMMARY OF QUANTITIES

ROUTE NO	SECTION	COUNTY	TOTAL SHEETS	THIS SHEET
F.A.U. 6728	*	TAZEWELL	28	4

FED. RD. DIST NO. ILLINOIS PROJECT TE-0004(110)

*10-00108-00-BT
CONTRACT NO. 89598

CODE NUMBER	ITEM DESCRIPTION	UNITS	TOTAL QUANTITY	SP
20200100	EARTH EXCAVATION	CU YD	743	
20400800	FURNISHED EXCAVATION	CU YD	654	SP
25000100	SEEDING, CLASS 1	ACRE	0.80	SP
25000300	SEEDING, CLASS 3	ACRE	0.20	
25000400	NITROGEN FERTILIZER NUTRIENT	LB	90	
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	LB	90	
25000600	POTASSIUM FERTILIZER NUTRIENT	LB	90	
25100115	MULCH METHOD 2	ACRE	1	
28000400	PERIMETER EROSION BARRIER	FOOT	475	
35101800	AGGREGATE BASE COURSE, TYPE B, 6"	SQ YD	3,579	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	895	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	401	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	125	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	SQ FT	1,376	
42400800	DETECTABLE WARNINGS	SQ FT	246	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	117	
542D5491	PIPE CULVERTS, CLASS D, TYPE 1, EQUIVALENT ROUND - SIZE 36"	FOOT	72	SP
56109210	WATER VALVES TO BE ADJUSTED	EACH	4	*
60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SQ FT	300	*
66400205	CHAIN LINK FENCE, 5'	FOOT	145	
67100100	MOBILIZATION	L SUM	1	
72000100	SIGN PANEL - TYPE 1	SQ FT	17.26	
72900100	METAL POST - TYPE A	FOOT	54	
** 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	820	
** 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	144	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	235	
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	300	*
X4402810	ISLAND SURFACE REMOVAL AND REPLACEMENT	SQ FT	99	*
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	*
X7240505	RELOCATE SIGN PANEL AND POST	EACH	5	*
Z0043750	PRECAST MODULAR BLOCK WALL	SQ FT	126	*
Z0062000	SAW CUTTING	FOOT	115	*
** 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA	FOOT	32	
** 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO 14 7C	FOOT	901	
** 87500600	TRAFFIC SIGNAL POST, 10 FT	EACH	1	SP
** 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3	
** 87900200	DRILL EXISTING HANDHOLE	EACH	1	
** 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED W/COUNTDOWN TIMER	EACH	4	SP
** 88800100	PEDESTRIAN PUSH-BUTTON	EACH	4	SP
** 89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1	*
	* SPECIAL PROVISIONS			
	** SPECIALTY ITEMS			
	SP ADDITIONAL SPECIAL PROVISIONS			

SUMMARY OF QUANTITIES		AUSTIN ENGINEERING, CO., INC	
NORTH CUMMINGS LANE		Consulting Engineers / Surveyors	
RECREATION TRAIL NORTH LOOP		8100 North University Street	
FOR CITY OF WASHINGTON		Peoria Illinois 61615-1879	
DATE 12/01/11	SCALE	BOOK	PROJECT NUMBER 20-10-008
			SHEET NO 4 OF 23