

PIPE CULVERT SCHEDULE

STA	PIPE CULVERTS CLASS A TYPE 1 EQUIVALENT ROUND SIZE	PIPE CULVERTS CLASS A TYPE 1 EQUIVALENT ROUND SIZE	PIPE CULVERTS CLASS A TYPE 1	PIPE CULVERTS CLASS D TYPE 1	PIPE CULVERTS CLASS D TYPE 1 EQUIVALENT ROUND SIZE	PIPE CULVERTS CLASS D TYPE 1 EQUIVALENT ROUND SIZE	PIPE CULVERTS CLASS A TYPE 1	PIPE CULVERTS CLASS D TYPE 1	PIPE CULVERTS CLASS D TYPE 1	PRECAST REINFORCED CONCRETE FLARED END SECTIONS EQUIVALENT ROUND SIZE	PRECAST REINFORCED CONCRETE FLARED END SECTIONS EQUIVALENT ROUND SIZE	PRECAST REINFORCED CONCRETE FLARED END SECTIONS	PRECAST REINFORCED CONCRETE FLARED END SECTIONS
AR 9+15	36"	30"	24"	15"	15"	18"	30"	18"	24"	36"	30"	24"	30"
LT 15+36	53 FT					34 FT				2			
LT 29+00				44 FT									
RT 29+00				42 FT									
RT 34+70								44 FT					
AR 35+20		40 FT									2		
RT 47+88								52 FT					
LT 48+25				46 FT									
AR 48+51			53 FT									2	
LT 48+78				46 FT									
RT 53+03					42 FT								
LT 54+90					48 FT								
LT 55+45					48 FT								
LT 56+76				52 FT									
LT 58+48				68 FT									
AR 60+10			56 FT									2	
AR 75+91							68 FT						2
LT 77+65								48 FT					
LT 79+50									54 FT				
AR 79+80							48 FT						
LT 86+92				48 FT									2
LT 88+60					52 FT								
TOTALS	53 FT	40 FT	109 FT	346 FT	190 FT	34 FT	116 FT	144 FT	54 FT	2 EA	2 EA	4 EA	4 EA

STORM SEWER SCHEDULE

LOCATION	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	STORM SEWER CLASS A TYPE 1 18"	MANHOLE TYPE A 4' DIAMETER WITH TYPE 1 FRAME CLOSED LID	STORM SEWER CLASS A TYPE 1 12"	INLET TYPE A TYPE 8 GRATE	STORM SEWER CLASS A TYPE 1 15"
STA 35+19 35' LT	1.0					
STA 35+19 TO 30+00 35' LT		510.0				
STA 30+00 35' LT			1.0			
STA 30+00 TO 26+00 30' LT		398.0				
STA 26+00 30' LT			1.0			
STA 26+00 30' LT TO 21' LT				7.0		
STA 26+00 21' LT					1.0	
STA 26+00 21' LT TO 21' RT				42.0		
STA 26+00 21' RT					1.0	
STA 26+00 TO 22+00 30' LT						398.0
STA 22+00 30' LT			1.0			
STA 22+00 30' LT TO 21' LT				6.0		
STA 22+00 21' LT					1.0	
STA 22+00 21' LT TO 21' RT				42.0		
STA 22+00 21' RT					1.0	
STA 22+00 TO 19+00 30' LT						296.0
STA 19+00 30' LT			1.0			
STA 19+00 30' LT TO 21' LT				6.0		
STA 19+00 21' LT					1.0	
STA 19+00 21' LT TO 21' RT				41.0		
STA 19+00 21' RT					1.0	
TOTALS	1.0 EACH	908 FOOT	4.0 EACH	144 FOOT	6.0 EACH	694 FOOT

INLET & PIPE PROTECTION SCHEDULE

STA	O/S	QTY
9+15	RT	1
15+53	LT	1
19+00	LT	1
19+00	RT	1
22+00	LT	1
22+00	RT	1
28+78	LT	1
28+79	RT	1
34+48	RT	1
35+20	LT	1
47+62	RT	1
48+02	LT	1
48+51	LT	1
48+99	LT	1
53+24	RT	1
54+69	LT	1
56+50	LT	1
58+14	LT	1
75+68	LT	1
77+41	LT	1
79+23	LT	1
79+80	LT	1
87+16	LT	1
88+76	LT	1
TOTAL	24 EACH	

TRENCH BACKFILL SCHEDULE

LOCATION	QUANTITY
AR 9+15	3 CU YD
AR 19+00	2 CU YD
AR 22+00	3 CU YD
AR 26+00	3 CU YD
AR 35+50	4 CU YD
AR 48+51	7 CU YD
AR 60+10	9 CU YD
AR 75+91	8 CU YD
AR 79+80	12 CU YD
TOTAL	51 CU YD

GRADING & SHAPING DITCHES SCHEDULE

LOCATION	O/S	QUANTITY
48+51	RT	88 FT
79+80	RT	95 FT
TOTAL		183 FT

STONE RIPRAP CLASS A-3 SCHEDULE

LOCATION	QUANTITY
9+15 LEFT	111 TONS
79+80 RIGHT	46 TONS
TOTAL	157 TONS

SHELBY COUNTY
NEOGA ROAD PROJECT
F.A.S. 656
SECTION 09-00271-00-RS
DETAILS