

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
656	09-00271-00-RS	SHELBY	62	58

NEOGA PROJECT
CONTRACT NO 95670

RATES OF APPLICATIONS

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES.

THESE RATES MAY BE ADJUSTED BY THE ENGINEER IN THE FIELD.

BITUMINOUS MATERIALS (PRIME COAT) = 0.10 GAL/SQ.YD.

AGGREGATE (PRIME COAT) = 5.0 LBS/SQ.YD.

HOT-MIX ASPHALT = 112 LBS/SQ.YD./INCH

AGGREGATE SHOULDERS = 2.10 TONS/CU.YD.

AGGREGATE SURFACE COURSE = 2.10 TONS/CU.YD.

GENERAL NOTES FOR RESURFACING

WHEREVER IN THE PLANS OR SPECIFICATIONS THE TERM STANDARD SPECIFICATIONS IS USED, IT SHALL BE UNDERSTOOD BY THE CONTRACTOR TO MEAN THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AS PREPARED BY THE DEPARTMENT OF TRANSPORTATION OF THE STATE OF ILLINOIS AND ADOPTED JANUARY 1, 2012.

ALL ELEVATIONS SHOWN ARE IN REFERENCE TO AN ASSUMED DATUM.

WHERE SECTION, SUB-SECTION MARKERS, OR U.S. ARMY CORPS OF ENGINEER MARKERS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE DEPARTMENT AND AUTHORIZED AGENT OR LAND SURVEYOR HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.

FOR THE SUGGESTED SEQUENCE OF OPERATIONS SEE THE CONTRACT SPECIAL PROVISIONS.

EXISTING ROAD SIGNS THAT CONFLICT WITH CONSTRUCTION OPERATIONS SHALL BE COVERED OR REMOVED AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPERATELY BUT SHALL BE INCLUDED IN THE COST OF THE CONTRACT PAY ITEMS AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED THE CONTRACTOR.

ALL STREET RETURNS SHALL HAVE RADII MEASURED TO THE EDGE OF THE PAVEMENT UNLESS OTHERWISE NOTED ON THE PLANS.

ACCESS TO ALL ENTRANCES SHALL BE MAINTAINED AT ALL TIMES DURING THE CONSTRUCTION OF THIS SECTION.

EXCEPT WHERE DESIGNATED OTHERWISE, THE LOCATIONS AND/OR DEPTHS OF UNDERGROUND UTILITIES SHOWN HAVE BEEN TAKEN FROM INFORMATION FURNISHED BY THE UTILITY OWNERS & MUST BE CONSIDERED APPROXIMATE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL UNDERGROUND UTILITIES. CONTACT J.U.L.I.E., PHONE 800-892-0123, AND ALL UTILITY COMPANIES PRIOR TO DIGGING.

THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES 48 HOURS PRIOR TO EXCAVATION OPERATIONS.

THE CONTRACTOR SHALL TAKE REASONABLE PRECAUTIONS TO PROTECT PUBLIC AND PRIVATE PROPERTY. IF AT ANY TIME THE CONTRACTOR DAMAGES OR DESTROYS PUBLIC OR PRIVATE PROPERTY, THE CONTRACTOR SHALL, AT HIS OWN EXPENSE, RESTORE SUCH PROPERTY TO A CONDITION EQUAL TO THAT EXISTING BEFORE SUCH DAMAGE.

EXISTING CONCRETE AND BUTUMINOUS CONCRETE PAVEMENT IN WHICH THE TOP SURFACE IS TO BE BUTT JOINED TO THE PROPOSED WORK SHALL BE SO JOINED THROUGH FULL DEPTH SAW CUT JUNCTIONS. THIS WORK SHALL BE CONSIDERED AS INCLUDED IN THE CONTRACT, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED THE CONTRACTOR.

THE CONTRACTOR SHALL PROVIDE INTERNET ACCESS TO THE BITUMINOUS PLANT QUALITY CONTROL LAB SO THAT BITUMINOUS CONCRETE PLANT REPORTS CAN BE E-MAILED TO THE ILLINOIS DEPARTMENT OF TRANSPORTATION DISTRICT HEADQUARTERS. THIS WORK SHALL BE INCLUDED IN THE COST OF ALL BITUMINOUS ITEMS.

THE RESIDENT ENGINEER SHALL BE THE SOLE JUDGE CONCERNING THE CURING TIME FOR THE VARIOUS BITUMINOUS LIFTS.

MAILBOX TURNOUTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH I.D.O.T. STANDARD B.L.R. 24.

THE CONTRACTOR SHALL NOTIFY THE SHELBY COUNTY HIGHWAY DEPARTMENT RESIDENT ENGINEER AND THE COUNTY ENGINEER 72 HOURS IN ADVANCE OF CONSTRUCTION WORK.

SHELBY COUNTY
 NEOGA ROAD PROJECT
 F.A.S. 656
 SECTION 09-00271-00-RS
 DETAILS