

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

Summary of Quantities

Various Routes  
OVD SIN STR REP & REPL 2006-9  
Various Counties  
Sheet 2 of 114  
Contract Number 44904

CODE NUMBER	PAY ITEM	UNIT	Y002 - 1C 100% STATE TOTAL QUANTITY	URBAN	RURAL
T9990700	REPLACE OVERHEAD SIGN WALKWAY	FOOT	36.00		36.00
T9990710	REMOVE & REINSTALL WALKWAY	FOOT	601.50	125.00	476.50
T9992300	OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	529.00	245.00	284.00
T9992530	REPLACE/TIGHTEN CLIPS PER SIGN	EACH	6.00		6.00
T9992700	REMOVE & REINSTALL SIGN PANEL	SQ FT	5,478.00	1,185.50	4,292.50
T9995010	REMOVE & RE-ERECT OVERHEAD SIGN END SUPPORT	EACH	2.00		2.00
T9995200	REPLACE U-BOLT	EACH	16.00		16.00
T9995400	FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	24.00	12.00	12.00
T9996200	REPAIR CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE	EACH	4.00	1.00	3.00
T9996300	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	69.00	30.00	39.00
T9997250	FURNISH & INSTALL INTERNAL TRUSS CLAMP	EACH	1.00		1.00
T9997255	FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	12.00	4.00	8.00
T9997700	FURNISH & INSTALL SAFETY CHAIN	EACH	48.00	6.00	42.00
T9998600	TIGHTEN CANTILEVER CONNECTION	EACH	4.00		4.00
T9998700	FURNISH & INSTALL WALKWAY TIE DOWN BOLT	EACH	1.00		1.00
T9998815	REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	60.00		60.00
T9998820	FURNISH & INSTALL HANDRAIL	FOOT	518.00	518.00	
T9998897	REPLACE HANDRAIL SUPPORT	EACH	2.00		2.00
T9998910	FURNISH & INSTALL METAL SCREEN	EACH	12.00	8.00	4.00
T9998995	DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	19.00	3.00	16.00