

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
Schedule of Quantities

Various Routes
OVD SIN STR REP & REPL 2006-9
Various Counties
Sheet 5 of 114
Contract Number 44904

PAY ITEM	UNIT	Y002 - 1C 100% STATE TOTAL QUANTITY	DISTRICT 1	DISTRICT 2	DISTRICT 3	DISTRICT 4	DISTRICT 5	DISTRICT 6	DISTRICT 7	DISTRICT 8
REPLACE OVERHEAD SIGN WALKWAY	FOOT	36.00		20.00			16.00			
REMOVE & REINSTALL WALKWAY	FOOT	601.50		29.50	220.00		150.50	59.00	17.00	125.50
REMOVE & RE-ERECT OVERHEAD SIGN END SUPPORT	EACH	2.00				2.00				
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	529.00	245.00	216.00		68.00				
REPLACE/TIGHTEN CLIP PER SIGN	EACH	6.00		4.00		1.00		1.00		
REMOVE & REINSTALL SIGN PANEL	SQ FT	5,478.00		700.00	1,652.00		1,169.75	468.00	302.75	1,185.50
REPLACE U-BOLT	EACH	16.00		4.00		12.00				
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	24.00	12.00	12.00						
REPAIR CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE	EACH	4.00	1.00			3.00				
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	69.00	26.00	8.00	20.00	7.00			4.00	4.00
FURNISH & INSTALL INTERNAL TRUSS CLAMP	EACH	1.00				1.00				
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	12.00	3.00	3.00		5.00			1.00	
FURNISH & INSTALL SAFETY CHAIN	EACH	48.00	4.00	10.00	8.00	10.00	8.00	2.00	4.00	2.00
TIGHTEN CANTILEVER CONNECTION	EACH	4.00				4.00				
FURNISH & INSTALL WALKWAY TIE DOWN BOLT	EACH	1.00				1.00				
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	60.00		9.00		33.00		6.00	12.00	
FURNISH & INSTALL HANDRAIL	FOOT	518.00	518.00							