

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Various Routes
OVD SIN STR REP & REPL 2006-9
Various Counties
Sheet 24 of 114
Contract Number 44904

District 2
Schedule of Locations for Overhead Sign Structure Replacement

Location No.:	2-01	State I.D. No.:	2S101U020R009.5		
County:	Winnebago	Route:	US 20	M.P.:	9.5
				Direction:	EB
Description of Work	Unit	Quantity			
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00			
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00			
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00			
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	54.00			
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	5.00			
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	2.00			
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00			

Location No.:	2-04	State I.D. No.:	2S037I080L011.4		
County:	Henry	Route:	I - 80	M.P.:	11.4
				Direction:	WB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00			
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00			
OVERHEAD SIGN STRUCTURE-SPAN TYPE I-A	FOOT	50.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	12.00			
REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	4.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	432.00			
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00			
RELOCATE ELECTRIC SERVICE	EACH	1.00			
OVERHEAD SIGN STRUCTURE WALKWAY, SPECIAL	FOOT	38.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
REMOVE EXISTING LUMINAIRE	EACH	3.00			

Location No.:	2-02	State I.D. No.:	2S006I080R059.9		
County:	Bureau	Route:	I - 80	M.P.:	59.9
				Direction:	EB
Description of Work	Unit	Quantity			
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00			
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	1.00			
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00			
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00			
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	2.00			
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	21.50			
REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	2.00			
RELOCATE ELECTRIC SERVICE	EACH	1.00			
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	88.00			
OVERHEAD SIGN STRUCTURE WALKWAY, SPECIAL	FOOT	30.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
REMOVE EXISTING LUMINAIRE	EACH	2.00			

Location No.:	2-05	State I.D. No.:	2S050I080R073.4		
County:	LaSalle	Route:	I - 80	M.P.:	73.4
				Direction:	EB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00			
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00			
OVERHEAD SIGN STRUCTURE-SPAN TYPE I-A	FOOT	84.00			
REMOVE & REINSTALL WALKWAY	FOOT	29.50			
REMOVE & REINSTALL SIGN PANEL	SQ FT	268.00			
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	20.40			
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00			
RELOCATE ELECTRIC SERVICE	EACH	1.00			
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			

Location No.:	2-03	State I.D. No.:	2S037I080L010.2		
County:	Henry	Route:	I - 80	M.P.:	10.2
				Direction:	WB
Description of Work	Unit	Quantity			
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00			
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00			
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00			
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00			
REPLACE U-BOLT	EACH	4.00			
REPLACE HANDRAIL SUPPORT	EACH	2.00			
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00			
REPLACE OVERHEAD SIGN WALKWAY	FOOT	20.00			
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	74.00			