

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Various Routes
OVD SIN STR REP & REPL 2006-9
Various Counties
Sheet 104 of 114
Contract Number 44904

District 8
Schedule of Locations for Truss Repair & Replacement

Location No.:	8-01	State I.D. No.:	8S060I055L017.2		
County:	Madison	Route:	I - 55	M.P.:	17.2
				Direction:	WB
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE - SPAN, TYPE II A		FOOT	80.00		
FURNISH & INSTALL METAL SCREEN		EACH	4.00		
DISCONNECT / RECONNECT ELECTRIC SERVICE		EACH	1.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	472.50		
REMOVE & REINSTALL WALKWAY		FOOT	39.00		
This truss is being downsized from a Type IV truss to a Type II truss. The existing end supports will be used.					
All work must be completed during District 8 non-peak hours.					

Location No.:	8-03	State I.D. No.:	8S060I055L018.3		
County:	Madison	Route:	I - 55	M.P.:	18.3
				Direction:	WB
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE - SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE - SPAN, TYPE II A		FOOT	70.00		
FURNISH & INSTALL METAL SCREEN		EACH	4.00		
DISCONNECT / RECONNECT ELECTRIC SERVICE		EACH	1.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	336.00		
REMOVE & REINSTALL WALKWAY		FOOT	42.00		
This truss is being downsized from a Type IV truss to a Type II truss. The existing end supports will be used.					
All work must be completed during District 8 non-peak hours.					

Location No.:	8-02	State I.D. No.:	8S082S003L004.4		
County:	St. Clair	Route:	IL - 3	M.P.:	4.4
				Direction:	SB
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE - SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE - SPAN TYPE IIA		FOOT	84.00		
OVERHEAD SIGN SUPPORT GROUT REPAIR		EACH	4.00		
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00		
DISCONNECT / RECONNECT ELECTRIC SERVICE		EACH	1.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	377.00		
REMOVE & REINSTALL WALKWAY		FOOT	44.50		
This truss is being downsized from a Type IV truss to a Type II truss. The existing end supports will be used.					
All work must be completed during District 8 non-peak hours.					