

F.A.I. RTE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(32, 47-4)K	KENDALL/GRUNDY	243	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			
CONTRACT NO. 66294				

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE					
				90% FED ROADWAY 10% STATE		50% STATE 50% MINOOKA		HIGHWAY LIGHTING	
				J000-2A (KENDALL)	J000-2A (GRUNDY)	SFTY-1B (KENDALL)	SFTY-1B (GRUNDY)	Y030-1E (KENDALL)	Y030-1E (GRUNDY)
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	26,184	14,822	11,362				
42001300	PROTECTIVE COAT	SQ YD	39,759	22,047	17,712				
42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	SQ YD	9,384	5,105	4,279				
X0325237	TRANSVERSE TERMINAL JOINT COMPLETE, 12'	EACH	2	1	1				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 8 INCH	SQ YD	1,337	487	850				
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	7,205			2,387	4,818		
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	701	245	456				
44000100	PAVEMENT REMOVAL	SQ YD	26,894	13,635	13,259				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,235	907	328				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,577	535	2,042				
44000600	SIDEWALK REMOVAL	SQ FT	289	0	289				
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	6,517	3,406	3,111				
44004000	PAVED DITCH REMOVAL	FOOT	681	632	49				
44213200	SAW CUTS	FOOT	5,189	2,924	2,265				
48100300	AGGREGATE SHOULDERS, TYPE A 4"	SQ YD	516	516	0				
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	2,123	1,232	891				
48300500	PORTLAND CEMENT CONCRETE SHOULDERS, 10"	SQ YD	4,439	2,349	2,090				
50102400	CONCRETE REMOVAL	CU YD	14.1	1.7	12.4				
50104400	CONCRETE HEADWALL REMOVAL	EACH	10	5	5				
50104650	SLOPE WALL REMOVAL	SQ YD	204	100	104				
50105200	REMOVE EXISTING CULVERTS	EACH	1	1	0				
50105210	REMOVE EXISTING CULVERTS	FOOT	206	101	105				
50200100	STRUCTURE EXCAVATION	CU YD	2,875	75	2,800				
50300225	CONCRETE STRUCTURES	CU YD	49.5	24.9	24.6				
50800105	REINFORCEMENT BARS	POUND	135,430	1,840	133,590				
51205200	TEMPORARY SHEET PILING	SQ FT	4,760	0	4,760				
54001003	BOX CULVERT END SECTIONS, CULVERT NO. 3	EACH	1	1	0				
54001004	BOX CULVERT END SECTIONS, CULVERT NO. 4	EACH	2	2	0				
54002080	EXPANSION BOLTS 3/4 INCH X 18 INCH	EACH	16	16	0				
54003000	CONCRETE BOX CULVERTS	CU YD	547.8	0.0	547.8				
54010805	PRECAST CONCRETE BOX CULVERT 8' X 5'	FOOT	96	96	0				
X0325249	PRECAST CONCRETE BOX CULVERT 7.5' X 2'	FOOT	72	72	0				

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 80 (I-80 AT MINOOKA INTERCHANGE)

SUMMARY OF QUANTITIES

SCALE: NONE

DRAWN BY: NJS

DATE: 2/10/06

CHECKED BY: JJC

