

← 90% FED 10% STATE →

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(32, 47-4)K	KENDALL/GRUNDY	243	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 66294				

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QTY.	ROADWAY		TRAFFIC SIGNALS		HIGHWAY LIGHTING	
				J000-2A (KENDALL)	J000-2A (GRUNDY)	Y031-1F (KENDALL)	Y031-1F (GRUNDY)	Y030-1E (KENDALL)	Y030-1E (GRUNDY)
* X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	1,982			991	991		
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1,353			681	672		
△ X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	585			226	359		
* X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	15			7	8		
* X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4			2	2		
* X8801345	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	1			1			
* X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	7			4	3		
* X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1				1		
* X8810610	PEDESTRIAN SIGNAL HEAD, L.E.D., 1-FACE, BRACKET MOUNTED	EACH	4			2	2		
XX001854	STABILIZED SUB-BASE 6'	SQ YD	12,651	6,904	5,747				
XX003503	FLARED END SECTION REMOVAL	EACH	3	1	2				
XX004201	PAVEMENT REINFORCEMENT 14"	SQ YD	9,384	5,105	4,279				
* XX005430	MAINTENANCE OF EXISTING HIGHWAY LIGHTING	L SUM	1					0.5	0.5
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	46,756	25,244	21,512				
Z0002600	BAR SPLICERS	EACH	305	0	305				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5				
Z0013825	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	61	0	61				
Z0028700	GRANULAR SUBGRADE REPLACEMENT	CU YD	1,205	695	510				
□ Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	1	1	0				

PATRICK
ENGINEERING INC.
LISLE, ILLINOIS

* SPECIALTY ITEM △ 100% COST TO THE VILLAGE OF MINOOKA (Y031-3D) □ SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 80 (I-80 AT MINOOKA INTERCHANGE)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY:
DATE: 2/10/06 CHECKED BY: JUC