

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(32, 47-4)K	KENDALL/GRUNDY	243	23
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 66294				

ITEM 66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS			
STATION	OFFSET	LT / RT	EACH
RAMP A			
400+53.86	77.2	RT	1
404+27.71	77.6	RT	1
406+00.00	147.1	RT	1
406+91.75	147.1	RT	1
410+17.58	49.6	RT	1
416+22.72	39.2	RT	1
417+22.72	54.2	RT	1
418+97.72	54.2	RT	1
419+97.72	39.2	RT	1
RAMP B			
390+40.65	28.9	RT	1
396+36.71	65.2	RT	1
399+35.75	42.7	RT	1
RAMP C			
187+49.76	28.9	RT	1
191+97.85	65.2	RT	1
191+96.83	42.7	RT	1
192+17.35	44.1	RT	1
193+30.69	82.1	RT	1
195+00.54	77.2	RT	1
197+05.36	68.7	RT	1
197+60.84	54.5	RT	1
RAMP D			
206+66.72	49.2	RT	1
207+97.73	52.8	RT	1
208+42.99	60.8	RT	1
208+55.72	54.0	RT	1
214+66.53	88.4	RT	1
214+89.28	21.8	RT	1
220+43.09	93.8	RT	1
220+49.12	84.2	RT	1
TOTAL			28

ITEM 44000500 COMBINATION CURB AND GUTTER REMOVAL					
LOCATION	STATION	TO	STATION	LT / RT	LENGTH (FT)
RIDGE	998+62.92	TO	1007+07.75	RT	845
RIDGE	1000+30.00	TO	1002+70.50	LT	241
RIDGE	1002+70.50	TO	1003+23.74	LT	81
OTTAWA	1003+22.45	TO	OTTAWA	LT	194
OTTAWA	1003+62.96	TO	OTTAWA	RT	124
OTTAWA	1003+81.78	TO	OTTAWA	RT	118
RIDGE	1003+81.78	TO	1005+14.42	LT	167
RIDGE	1005+28.83	TO	1005+52.17	LT	74
RIDGE	1005+68.95	TO	1007+04.28	LT	166
RIDGE	1004+74.54	TO	DRIVEWAY	RT	35
RIDGE	1016+91.96	TO	DRIVEWAY	LT	27
RIDGE	1017+66.21	TO	DRIVEWAY	RT	62
RIDGE	1017+59.23	TO	DRIVEWAY	LT	126
RIDGE	1018+31.65	TO	DRIVEWAY	RT	167
RIDGE	1018+79.05	TO	DRIVEWAY	LT	53
RIDGE	1019+38.00	TO	DRIVEWAY	LT	40
RIDGE	1019+66.31	TO	DRIVEWAY	RT	60
TOTAL					2,577

ITEM 70500625 TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 2					
LOCATION	STATION	TO	STATION	LT / RT	EACH
RIDGE	1006+92.56	TO	1007+01.04	RT	1
RAMP C	199+12.50	TO	199+25.00	LT	1
TOTAL					2

ITEM 70500615 TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1					
LOCATION	STATION	TO	STATION	LT / RT	EACH
RIDGE	1005+77.91	TO	1006+27.91	RT	1
RAMP C	194+75.00	TO	195+25.00	LT	1
TOTAL					2

ITEM 70500100 TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A					
LOCATION	STATION	TO	STATION	LT / RT	LENGTH (FT)
RIDGE	1006+27.91	TO	1006+92.56	RT	75.0
RAMP C	195+25.00	TO	199+12.50	LT	387.5
TOTAL					462.5

ITEM 63000025 STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES					
LOCATION	STATION	TO	STATION	LT / RT	LENGTH (FT)
RAMP B	397+62.50	TO	397+75.00	RT	12.5
TOTAL					12.5

ITEM 60618320 CONCRETE MEDIAN SURFACE, 6 INCH				
LOCATION	STATION	TO	STATION	AREA (SQ FT)
RIDGE ROAD	1004+61.67	TO	1007+79.20	3,586
RIDGE ROAD	1014+27.34	TO	1015+86.04	1,506
TOTAL				5,092

ITEM 60624600 CORRUGATED MEDIAN				
LOCATION	STATION	TO	STATION	AREA (SQ FT)
RIDGE ROAD	1003+80.00	TO	1005+30.00	1,070
RIDGE ROAD	1015+63.00	TO	1016+80.00	778
TOTAL				1,849

ITEM 60620300 CONCRETE MEDIAN, TYPE SB-6.24 (SPECIAL)				
LOCATION	STATION	TO	STATION	AREA (SQ FT)
RIDGE ROAD	1008+64.45	TO	1011+00.00	1,206
RIDGE ROAD	1011+00.00	TO	1013+35.04	1,358
TOTAL				2,564

ITEM Z0030255 IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2			
LOCATION	STATION	LT / RT	EACH
TEMP RAMP A	11+25.00	LT	1
TOTAL			1

ITEM 66900200 NON-SPECIAL WASTE DISPOSAL					
LOCATION	STATION	TO	STATION	LT / RT	CU YD
RIDGE	1003+50	TO	1004+30	RT	55
RIDGE	1016+00	TO	1017+50	LT	187
TOTAL					242

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAI ROUTE 80 (I-80 AT MINOOKA INTERCHANGE)
NAME	DATE	
		SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: 2/10/06
DRAWN BY: NJS
CHECKED BY: JJC

