

CULVERT AND STORM SEWER SCHEDULE

STATION	TYPE	TRENCH BACKFILL CU. YD.	PIPE CULVERTS, CLASS A, TYPE 1 (TEMPORARY)			STORM SEWERS, CLASS A										P.R.C. FLARED END SECTIONS				MANHOLE TYPE A, TYPE 1 FRAME					CATCH BASINS			CONCRETE HEADWALL FOR PIPE DRAINS EA.									
			12"	24"	36"	TYPE 1		TYPE 2						TYPE 3	P.R.C. FLARED END SECTIONS				CLOSED LID		OPEN LID			CLOSED LID, RESTRICTOR PLATE		TYPE A, 4' DIA.			TYPE C								
			L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.		EA.	EA.	EA.	EA.	EA.				
LT 1012+10	CATCH BASIN																																			1	
LT 1012+10 TO 1012+06	STORM SEWER					27																															
LT 1013+62	MANHOLE																				1																
LT 1013+62 TO 1012+05	STORM SEWER	45.8							152																												
LT 1014+90	MANHOLE																				1																
LT 1014+90 TO 1013+62	STORM SEWER	42.0							124																												
RT 1015+00	CATCH BASIN																																		1		
RT 1015+00 TO 1014+90	STORM SEWER	13.8				83																															
LT 1015+04	CATCH BASIN																																		1		
LT 1015+04 TO 1014+90	STORM SEWER	8.8				44																															
LT 1016+70	MANHOLE																				1																
LT 1016+70 TO 1014+90	STORM SEWER	53.5						176																													
LT 1016+75	CATCH BASIN																																			1	
RT 1016+75	CATCH BASIN																																		1		
LT 1016+75 TO 1016+70	STORM SEWER	2.4				16																															
LT 1016+75 TO 1016+70	STORM SEWER	10.5				55																															
LT 1019+20	MANHOLE																				1																
LT 1019+20 TO 1016+70	STORM SEWER	82.3				246																															
LT 1019+25	CATCH BASIN																																			1	
LT 1019+25 TO 1019+20	STORM SEWER	1.0				7																															
RT 1019+55	CATCH BASIN																																			1	
RT 1019+55 TO 1019+20	STORM SEWER	11.2				64																															
RAMP A																																					
LT 403+10	HEADWALL																																			1	
RT 403+11	HEADWALL																																			1	
LT 403+50	CATCH BASIN																																		1		
LT 403+50 TO 406+22	STORM SEWER								265																												
RT 406+00	HEADWALL																																			1	
RT 413+00	HEADWALL																																			1	
RT 418+00	HEADWALL																																			1	
RT 418+38	FLARED END SECTION																			1																	
RT 418+38 TO 418+38	STORM SEWER												3																								
RT 420+00	HEADWALL																																			1	
RAMP B																																					
RT 381+40	HEADWALL																																			1	
RT 384+50	HEADWALL																																			1	
RT 386+90	HEADWALL																																			1	
LT 388+00	CATCH BASIN																																		1		
LT 388+00 TO 391+00	STORM SEWER	36.8				299																															
LT 391+00	FLARED END SECTION																			1																	
LT 393+50	HEADWALL																																			1	
RT 393+68	HEADWALL																																			1	
RT 398+33	HEADWALL																																			1	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAI ROUTE 80 (I-80 AT MINOOKA INTERCHANGE)
NAME	DATE	
		SCHEDULE OF QUANTITIES
		SCALE: NONE
		DATE: 2/10/06
		DRAWN BY: NJS
		CHECKED BY: JJC

