

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(32, 47-41K)	KENDALL/GRUNDY	243	30
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 66294				

PAVEMENT MARKING TAPE, TYPE III							
LOCATION	LETTERS & SYMBOLS	LINE - 4"		LINE - 6"	LINE - 8"	LINE - 12"	LINE - 24"
		WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE
	SQ FT	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.
STAGE 1							
RIDGE ROAD		1478	2372			86	
OTTAWA DRIVE							
RAMP A		919	381				
RAMP B		701	84				
RAMP C		1076	560				
RAMP D							
STAGE 1A							
RIDGE ROAD		912	206	103			19
OTTAWA DRIVE							
RAMP A							
RAMP B	31						42
RAMP C	31	2308	651	199			
RAMP D							
STAGE 1B							
RIDGE ROAD		312	354				
OTTAWA DRIVE							
RAMP A							
RAMP B				78			
RAMP C	31	1039	380				
RAMP D							
STAGE 2							
RIDGE ROAD	47	4185	7137	688		273	108
OTTAWA DRIVE							
RAMP A							
RAMP B	31			358			35
RAMP C	62	135	3200	312			56
RAMP D		1382	2455				
STAGE 2A							
RIDGE ROAD	16	303	96	400			
OTTAWA DRIVE							
RAMP A							
RAMP B							
RAMP C							
RAMP D							
STAGE 3							
RIDGE ROAD	62		7549	1171			117
OTTAWA DRIVE							
RAMP A							
RAMP B				829			18
RAMP C				356			
RAMP D							
TAPE, TYPE III IN CASE OF COLD WEATHER PREVENTING PERMANENT MARKINGS		546	15,599	2,630	11,322	2,965	335
TOTALS		858	55,774	7,124	11,322	3,324	731

POLYUREA PAVEMENT MARKING, TYPE II								
LOCATION	LETTERS & SYMBOLS	LINE - 4"		LINE - 6"	LINE - 8"	LINE - 12"	LINE - 24"	
		WHITE	YELLOW	WHITE	WHITE	WHITE	YELLOW	WHITE
	SQ FT	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.
RIDGE ROAD	281	2851	1973	1410	892		49	256
OTTAWA DRIVE	31		96					
RAMP A		2234	729	182	2457	730		
RAMP B	140	1737	1065	501	2585	648		42
RAMP C	94	1544	795	537	2808	1096		38
RAMP D		1868	705		2581	442		
SUB-TOTALS		10,234	5,364			2,915	49	
TOTALS		546	15,598	2,629	11,322	2,965		336

TEMPORARY PAVEMENT MARKINGS							
LOCATION	LETTERS & SYMBOLS	LINE - 4"		LINE - 6"	LINE - 12"	LINE - 24"	
		WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE
	SQ FT	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.
STAGE 1							
RIDGE ROAD	31	4490	5784	250		306	97
OTTAWA DRIVE							12
RAMP A		647	511				
RAMP B	31	1059	653	43	160		22
RAMP C	31	794	548	66			88
RAMP D		767	792				
STAGE 1A							
RIDGE ROAD							36
STAGE 1A							
OTTAWA DRIVE							12
SUB-TOTALS		7,757	8,289		160	306	
TOTALS		94	16,046	360	467		267

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI ROUTE 80 (I-80 AT MINOOKA INTERCHANGE)  
 SCHEDULE OF QUANTITIES

SCALE: NONE  
 DATE: 2/10/06  
 DRAWN BY: NJS  
 CHECKED BY: JJC

**PATRICK**  
 ENGINEERING INC.  
 LISLE, ILLINOIS