

ITEM 42300400		
PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 8 INCH		
STATION	LT / RT	SQ YD
1017+26.92	LT	86
1018+13.36	RT	109
1018+58.93	LT	63
1019+20.26	RT	110
1020+69.72	LT	87
1022+67.67	LT	33
1001+41.73	LT	28
1001+41.73	RT	32
1004+07.97	RT	499
1005+41.11	LT	291
TOTAL		1,337

ITEM 66500105					
WOVEN WIRE FENCE, 4'					
LOCATION	STATION	TO	STATION	LT / RT	LENGTH (FT)
RAMPA	400+55.03	TO	410+17.58	RT	964
RAMP A	416+29.11	TO	419+91.08	RT	365
RAMP B	390+43.15	TO	399+33.57	RT	903
RAMP C	187+57.26	TO	196+18.52	RT	860
RAMP C	197+19.25	TO	197+59.01	RT	41
RAMP D	200+53.00	TO	208+53.59	RT	789
TOTAL					3,923

ITEM 42100380				
CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"				
LOCATION	STATION	TO	STATION	AREA (SQ YD)
RAMP A	408+98.98	TO	413+06.95	725
RAMP A	413+06.95	TO	416+06.86	400
RAMP A	416+06.86	TO	424+06.86	1,067
RAMP A	GORE AREA			588
RAMP B	384+35.33	TO	387+95.84	641
RAMP B	381+33.76	TO	384+35.33	536
RAMP B	GORE AREA			1,147
RAMP C	186+48.64	TO	190+09.15	641
RAMP C	183+34.37	TO	186+48.64	559
RAMP C	GORE AREA			816
RAMP D	208+93.59	TO	213+28.42	773
RAMP D	213+28.42	TO	216+28.42	400
RAMP D	216+28.42	TO	220+50.00	562
RAMP D	GORE AREA			528
TOTAL				9,383

ITEM 44000100	
PAVEMENT REMOVAL	
LOCATION	AREA (SQ YD)
RIDGE ROAD	9,742
RAMP A	5,072
RAMP B	4,043
RAMP C	3,321
RAMP D	4,717
TOTAL	26,894

ITEM 66502300					
WOVEN WIRE FENCE REMOVAL					
LOCATION	STATION	TO	STATION	LT / RT	LENGTH (FT)
RAMPA	1016+60.32	TO	410+02.75	RT	1,086
RAMP A	416+22.72	TO	419+97.72	RT	375
RAMP B	390+37.37	TO	399+35.75	RT	936
RAMP C	187+49.76	TO	197+60.84	RT	987
RAMP D	200+67.55	TO	208+55.72	RT	777
TOTAL					4,162

ITEM 28101400	
RIPRAP	
LOCATION	SQ YD
11' X 4' CULVERT	25
7.5' X 2' CULVERT	36
8' X 5' CULVERT	20
TOTAL	81

ITEM 44000920	
BITUMINOUS CONCRETE SHOULDER REMOVAL	
LOCATION	REA (SQ YD)
RAMP A	1,984
RAMP B	1,422
RAMP C	1,644
RAMP D	1,467
TOTAL	6,517

ITEM 28102500				
STONE RIPRAP DITCH				
STATION	TO	STATION	LT / RT	SQ YD
RAMP B				
398+35	TO	397+81	LT	235
RAMP D				
202+90	TO	202+60	LT	25
203+90	TO	203+60	RT	30
204+90	TO	204+60	LT	19
TOTAL				309

ITEM 42000501				
PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)				
LOCATION	STATION	TO	STATION	AREA (SQ YD)
RIDGE	1000+30.00	TO	1011+00.00	7,049
RIDGE	1011+00.00	TO	1025+50.00	9,317
OTTAWA	8+39.09	TO	RIDGE INTERSECTION	64
RAMP A	RIDGE INTERSECTION	TO	408+98.98	2,085
RAMP B	387+95.84	TO	RIDGE INTERSECTION	3,420
RAMP C	190+09.15	TO	RIDGE INTERSECTION	2,226
RAMP D	RIDGE INTERSECTION	TO	208+93.59	2,022
TOTAL				26,183

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 80 (I-80 AT MINOOKA INTERCHANGE)
 SCHEDULE OF QUANTITIES

SCALE: NONE
 DATE: 2/10/06

DRAWN BY: NJS
 CHECKED BY: JJC

