SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	LASALLE	95	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAP ROUTE 653 (ROUTE 18 COUPLE)
** SECTION (7)R, RS-2; (8)R, RS-1

	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	
	WEST BRIDGE STREET CONNECTOR		
	STA. 1102+10.80 33.13' LT.		1
	STA. 1102+10.80 24.20' RT.		1
	WASSON STREET		
	STA. 2404+20.00 15.00' LT.		1
	STA. 2406+73.41 31.44' RT.		1
		TOTAL	4
	MANHOLES, TYPE A, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	
	ALLEY		
	STA. 200+00		1
	STA. 202+32		1
	STA. 204+64		1
		TOTAL	3
	SANITARY SEWER, PVC SDR 35, 8"	FOOT	
	ALLEY		
	STA. 200+00-202+30		232
	STA. 202+32-204+64		232
		TOTAL	464
60236400	INLETS, TYPE A, TYPE 8 GRATE (24" DEPTH)	EACH	
	WEST MAINLINE		
	STAGE 1		
	31' RT. STA. 102+00 (TEMPORARY USE)		1
		TOTAL	1
60236600	INLETS, TYPE A, TYPE 9 FRAME AND GRATE	EACH	
	WEST MAINLINE		
	STA. 111+11.50 20.29' LT.		1
		TOTAL	1
60240303	INLETS, TYPE B, TYPE 9 FRAME AND GRATE	EACH	
	WASSON STREET		
	STA. 2403+18.00 33.21' RT.		1
		TOTAL	1
60255500	MANHOLES TO BE ADJUSTED	EACH	
	WEST MAINLINE		
	STA. 98+83 19.8' RT.		1
	STA. 98+92 19.9' RT.		1
	STA. 99+66 20.3' RT.		1
	STA. 99+75 20.0' RT.		1
	STA. 100+29 22.9' RT.		1
	STA. 101+67 15.0' RT.		1
	STA. 102+09 7.5' LT.		1
	STA. 110+17 8.3' RT.		1
	STA. 110+35 21.1' RT.		1
	STA. 110+39 17.5' LT.		1
	STA. 110+46 36.4' RT.		1
	STA. 110+53 3.9' LT.		1
	STA. 111+00 6.1' LT.		1
	WEST MAIN STREET CONNECTOR		
	STA. 1000+41 3.1' RT.		1
	STA. 1000+47 5.6' RT.		1
	STA. 1000+54 5.9' RT.		1
	WEST BRIDGE STREET CONNECTOR		
	STA. 111+00 12.1' RT.		1
	STA. 1101+11 0.1' RT.		1
	WASSON STREET		
	STA. 2406+58 1.3' RT.		1
	STA. 2408+70 45.6' RT.		1
		TOTAL	20
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	
	WEST MAINLINE		
	STA. 101+94 2.3' RT.		1
		TOTAL	1
60260100	INLETS TO BE ADJUSTED	EACH	
	WEST MAINLINE		
	STA. 99+15 42.0' RT.		1
	STA. 99+45 40.0' RT.		1
		TOTAL	2
60263105	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 3V FRAME AND GRATE	EACH	
	WEST MAINLINE		
	STA. 97+74 15.6' RT.		1
	STA. 97+84 15.5' RT.		1
	STA. 98+82 15.5' RT.		1
	STA. 100+30 15.4' RT.		1
		TOTAL	4
60500060	REMOVING INLETS	EACH	
	WEST MAINLINE		
	STA. 102+37 7.2' LT.		1
	STA. 110+99 12.5' LT.		1
	STA. 111+00 12.1' RT.		1
	WASSON STREET		
	STA. 2403+14 32.9' RT.		1
	STA. 2403+15 32.6' RT.		1
	STA. 2406+74 12.6' RT.		1
	STA. 2408+24 60.7' RT.		1
		TOTAL	7
60500305	FILLING INLETS	EACH	
	WEST MAINLINE		
	STA. 101+63 1.7' RT.		1
		TOTAL	1
60605000	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24	FOOT	
	WEST MAINLINE		
	RT. STA. 97+35-99+20		201.7
	RT. STA. 99+40-100+35		113.5
	RT. STA. 100+35-108+08		753.1
	LT. STA. 103+30-108+18		489.7
	LT. STA. 109+39-113+11		362.5
	RT. STA. 109+41-109+95		58.8
	RT. STA. 110+88-113+16		229.0
	WEST MAIN STREET CONNECTOR		
	LT. STA. 999+71-1001+02		108.7
	WEST BRIDGE STREET CONNECTOR		
	RT. STA. 1100+12-1102+46		271.8
	LT. STA. 1100+25-1102+45		227.6
	MURDOCK STREET		
	LT. STA. 303+21-303+81		71.0
	RT. STA. 303+21-303+66		67.5
	ALLEY		
	LT. STA. 500+23-500+73		76.5
	RT. STA. 500+26-500+75		78.2
60605000	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24 (CONT)	FOOT	
	WASSON STREET		
	LT. STA. 2403+08-2408+24		560.0
	RT. STA. 2403+08-2406+41		381.2
	RT. STA. 2406+63-2408+25		259.2
	LT. STA. 2408+68-2408+94		43.7
	RT. STA. 2408+69-2409+38		94.1
		TOTAL	4,447.8
60608600	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.06	FOOT	
	WEST MAIN STREET CONNECTOR		
	RT. STA. 1000+25-1000+70 (ISLAND MEDIAN)		53.1
	WASSON STREET		
	LT. STA. 2402+95-2403+12 (ISLAND MEDIAN)		20.0
	RT. STA. 2408+08-2408+23 (ISLAND MEDIAN)		23.1
		TOTAL	96.2
60609800	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.18	FOOT	
	WASSON STREET		
	RT. STA. 2408+24 (ISLAND MEDIAN)		17.2
		TOTAL	17.2
60610400	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.24	FOOT	
	WEST MAINLINE		
	LT. STA. 101+73-102+69 (ISLAND MEDIAN)		194.4
	WASSON STREET		
	LT. STA. 2402+95-2403+12 (ISLAND MEDIAN)		31.5
	RT. STA. 2408+08-2408+24 (ISLAND MEDIAN)		16.7
		TOTAL	242.6
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	S.F.	
	WEST MAINLINE		
	LT. STA. 101+85-102+68		2,253
	WASSON STREET		
	LT. STA. 2402+92-2403+12		124
	RT. STA. 2408+08-2408+24		153
		TOTAL	2,530
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL. MO.	
	COMPLETE		12
		TOTAL	12
70101700	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L. SUM	
	COMPLETE		1
		TOTAL	1
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	
	WHITE		
	WEST MAINLINE		
	STAGE 2		
	11'-54' RT. STA. 97+02-103+11		593.9
	16.5'-13.7' RT. STA. 110+62-113+91		334.0
	WASSON STREET		
	STAGE 1		
	11'-0' STA. 2403+47.5-2406+40.5		298.9
		SUB-TOTAL	1,226.8