

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
623	(30)I-1	LASALLE	12	3
FED. ROAD DIST. NO.		ILLINOIS		

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: Y007

CODE NO.	ITEM	UNIT	RURAL 100% STATE TOTAL QUANTITY
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	227
20400800	FURNISHED EXCAVATION	CU YD	227
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	53
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7
42001200	PAVEMENT FABRIC	SQ YD	67
44000013	BITUMINOUS SURFACE REMOVAL 5"	SQ YD	67
44000100	PAVEMENT REMOVAL	SQ YD	67
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	17
44100100	PAVEMENT REPLACEMENT	SQ YD	67
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	39
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	17
50102400	CONCRETE REMOVAL	CU YD	5.9
50300225	CONCRETE STRUCTURES	CU YD	5.9
50800105	REINFORCEMENT BARS	POUND	1100
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	284
58000110	MEMBRANE WATERPROOFING (SPECIAL)	SQ FT	432
63300205	REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	50
63300230	REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	20
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	482
70400100	TEMPORARY CONCRETE BARRIER	FOOT	290
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1530
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	260
78300100	PAVEMENT MARKING REMOVAL	SQ FT	419
X2510630	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	22
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	6
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	13
Z0018905	DRILL AND GROUT BARS	EACH	20
† Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2

† SFTY 3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 F.A.P. 623 (U.S. 6) SECTION (30)I-1  
 LASALLE COUNTY  
 STA. 1556+25

DATE 12/20/2005

DRAWN BY RLW

Date: 11/07/2005  
File: c:\projects\cmain06\cm324\detalls.dgn