CONTRACT NO. 68356

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	103N-1,TS	WARREN		5
STA.		TO STA.		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

STATUS OF UTILITIES

Frontier Communications

Route	Offset	Location	Type of Utility	Type of Conflict	Disposition
6th St.	36' Lt.	8+60	Telephone Pole	Sidewalk	Relocate
6th St.	37' Lt.	8+62	Telephone Pedestal	Sidewalk	Relocate
6th St.	42' Lt. to 46' Lt.	8+60 to 11+45	Buried Telephone	Curb & Gutter/Sub-base	Relocate
US 34	76' Lt. to 66' Lt.	427+45 to 427+70	Buried Fiber Optic	Ditch Cut	Relocate

AmerenIP (Gas)

Route	Offset	Location	Type of Utility	Type of Conflict	Disposition
6th St.	47' Lt. to 48' Lt.	8+60 to 11+45	Gas Main	Curb & Gutter/Sub-base	Relocate
US 34	65' Lt. to 65' Lt.	427+45 to 427+70	Gas Main	Ditch Cut	Caution

Insight

Route	Offset	Location	Type of Utility	Type of Conflict	Disposition
US 67	75 Ft.Rt.	15+64	Buried Cable TV	Sidewalk	Relocate
US 67	75 Ft.Rt.	17+48	Buried Cable TV	Curb & Gutter	Relocate

Monmouth Sanitary

Route	Offset	Location	Type of Utility	Type of Conflict	Disposition
6th St.	20' Rt.	12+33	Sanitary Manhole	Curb & Gutter	Relocate

AmerenIP (Electric)

Route	Offset	Location	Type of Utility	Type of Conflict	Disposition
6th St.	36 Ft.Lt.	8+60	Power Pole	Sidewalk	Relocate

PLOT DATE = 2/18/2006
FILE NAME = c:\pwworking\monmouth2\msaselvers.dgn
PLOT SCALE = 100.0000 ' / IN.
REFERENCE = REF

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STATUS OF UTILITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY JKW

CHECKED BY