

# SUMMARY OF QUANTITIES

F.A.P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	103N-1, TS	WARREN		10
STA.		TO STA.		
FED. ROAD DIST. NO. 8		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		FED - STATE 90 - 10 1000-1A	CITY 100 Y030-1E	SFTY - 3N IMPACT ATT. 90% FED 10% ST	FED-STATE-CITY 90 - 5 - 5 Y031-1F	
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	695.7	695.7				
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, 10"	SQ YD	243.1	243.1				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.3	1.3				
40600990	TEMPORARY RAMP	SQ YD	264.5	264.5				
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	97.3	97.3				
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	986.3	986.3				
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	2003.3	2003.3				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	126.1	126.1				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	511	511				
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	778.7	778.7				
44002800	ISLAND PAVEMENT REMOVAL	SQ YD	116.4	116.4				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	50.7	50.7				
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	304.3	304.3				
50102400	CONCRETE REMOVAL	CU YD	4.6	4.6				
54215979	REINFORCED CONCRETE PIPE ELBOW 24"	EACH	1	1				
54215985	REINFORCED CONCRETE PIPE ELBOW 30"	EACH	1	1				
54246205	INLET BOX, STANDARD 542526	EACH	1	1				
54248515	CONCRETE COLLAR	EACH	4	4				
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	26	26				

\* SPECIALTY ITEMS