

SUMMARY OF QUANTITIES

F. & P. SHEET	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	103N-1,7S	WARREN		12
STA.	TO STA.			
FED. ROAD DIST. NO. 4	ALWAYS	FED. AID PROJECT		

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		FED - STATE 90 - 10 1000-1A	CITY 100 Y030-1E	SFTY - 3N IMPACT ATT. 90% FED 10% ST.	FED-STATE-CITY 90 - 5 - 5 Y031-1F	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	160	160				
70300200	TEMPORARY PAVEMENT MARKING	FOOT	2867	2867				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	299	299				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	53.3	53.3				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	400	400				
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	299	299				
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	826	826				
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	2138	2138				
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	530.2	530.2				
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	153.3	153.3				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	61	61				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	35	35				
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	230				230	
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	114				114	
81012900	CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	109				109	
81021360	CONDUIT PUSHED, 3 1/2" DIA., PVC	FOOT	313				313	
81400400	CONCRETE HANDHOLE	EACH	3				3	
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	497				497	

* SPECIALTY ITEMS