

SUMMARY OF QUANTITIES

F. A. P. DIST.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	103N-1,TS	WARREN		13
STA.		TO STA.		
FEB. 1962 DIST. NO. 4		BLDG	FEB. 40 PROJECT	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		FED - STATE 90 - 10 1000-1A	CITY 100 Y030-1E	SFTY - 3N IMPACT ATT. 90% FED 10% ST.	FED-STATE-CITY 90 - 5 - 5 Y031-1F
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	802				802
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	2		2		
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	4				4
* 85700505	FULL-ACTUATED CONTROLLER IN EXISTING CABINET, SPECIAL	EACH	1				1
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	535.5				535.5
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3843				3843
87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 15 FT.	EACH	1				1
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1				1
87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1				1
87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT.	EACH	2				2
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3				3
87800415	CONCRETE FOUNDATION, TYPE E, 36 - INCH DIAMETER	FOOT	50				50
87900200	DRILL EXISTING HANDHOLE	EACH	5				5
88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	10				10
88800100	PEDESTRIAN PUSH-BUTTON	EACH	2				2

* SPECIALTY ITEMS