CONTRACT NO. 68356

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	103N-1,TS	WARREN		16
STA.		TO STA.		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

44000008- BIT. SURFACE REMOVAL 2.5"	
LOCATION	SQ YD
6th STREET	
STA. 8+53.8 (JOINT) TO 9+56 (MAINLINE E.O.P.)	958.01
STA. 11+64.2 (MAINLINE E.O.P.) TO 10+44.2	1045.28
TOTAL	2003.3

44000200 - DRIVEWAY PAVEMENT REMOVAL	
LOCATION	SQ YD
6th STREET	
RT. STA. 12+09	126.06
TOTAL	126.1

44000500 - COMB. CURB & GUTTER REMOVAL	
LOCATION	FOOT
6th STREET	
LT.STA. 6+51.78 - 9+53.47	127.3
LT. STA. 10+60.10 - 11+64.16	129.7
RT. STA. 12+68 - 427+80	253.6
TOTAL	511

44001430 - BITUMINOUS SHOULDER REMOVAL	
LOCATION	SQ YD
6th STREET	
RT. STA. 425+04 TO 425+97.19	111.0
LT. STA. 425+39.7 TO 425+94.67	63.4
LT. STA. 427+80 TO 432+16	515.6
STA. 426+30.1 - 426+59.1**	88.7
TOTAL	778.7

**The Median Area includes the pavement in the cost with shoulder removal.

44002800 - ISLAND PAVEMENT REMOVAL	
LOCATION	SQ YD
6th STREET	
LT. STA. 9+23.14 TO 9+51.52*	61.90
LT. STA. 10+53 TO 10+84.5*	54.52
TOTAL	116.4

*REMOVAL AREA'S MATCH LIMITS OF PROPOSED ISLANDS

50102400 - CONCRETE REMOVAL	
LOCATION	CU YD
6TH STREET	
LT. STA. 11+15.17 (EX. PAVED DITCH)	4.62
TOTAL	4.6

LOCATION	55101200- S.S. REM., 24"	55101400- S.S. REM., 30"
6th STREET	FOOT	FOOT
25.1' RT. STA. 11+05 - 30.5' RT. STA. 11+13.24	9	
30.5' RT. STA. 11+05 - 30.5' RT. STA. 11+47.09		40
30.5' RT. STA. 11+05 - 44.8' RT. STA. 11+04.3		14.3
TOTAL	9	54.3

60500060 - REMOVING INLETS	
LOCATION	EACH
6th STREET	
30.5' RT. STA. 11+05	1
TOTAL	1

70301000 - WORK ZONE PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
70300100 - SHORT-TERM	53.3
TOTAL	53.3

78300200 - RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
6TH ST.	
CENTERLINE - SOUTH	6
CENTERLINE - NORTH	3
ISLANDS	26
TOTAL	35

XX003503 - FLARED END SECTION REMOVAL	
LOCATION	EACH
6TH STREET	
LT. STA. 8+88.37	1
LT. STA. 9+39.01	1
TOTAL	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES REMOVAL

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 2/10/2006
FILE NAME = o:\projects\monmouth2\misasheets.dgn
PLOT SCALE = 100.0105 ' / IN.
USER NAME = wagerjo