

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	103N-1,TS	WARREN		20
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

COMBINATION CONCRETE CURB AND GUTTER		
LOCATION	#4001666- TYPE M-4.24 (SPECIAL)	60610800 - TYPE M-6.24 (SPECIAL)
	FOOT	FOOT
U.S. 34/6TH ST.-RADIUS		
(SW QUAD) RT. STA. 425+60.6 - LT. STA.		
(NW QUAD) LT. STA. 425+82 - LT. STA.		
(NE QUAD) RT. STA. 428+16 - RT. STA.		
6TH STREET-ISLANDS		
LT. STA. 9+27.26 TO 9+51.74 (SW QUAD)		74.5
LT. STA. 10+53 TO 10+84.5 (NW QUAD)	76.5	

PAVING SCHEDULE

LOCATION	35400500 - PCC BASE COURSE WIDENING, 10"	35300500 - PCC BASE COURSE, 10"	21001000 - GEO. TECH. FABRIC	42300300 - P.C.C. DRIVEWAY PAV'T, 7"	31100300 - SUB-BASE GRANULAR MATERIAL TYPE A 4"	31100700 - SUB-BASE GRANULAR MATERIAL TYPE A 8"	48101200 - AGGREGATE SHOULDER, TYPE B	48202600 - BITUMINOUS SHOULDERS, SUPER., 8"	40600200 - BITUMINOUS MATERIALS (PRIME COAT)			X4067100 - POLY. LEV. BINDER (MM), SUPER.,IL-4.75, N50	X4066538- POLY. BIT. CONC. SURF. CSE. SUPERPAVE MIX "E", N90, (1 1/2")
	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ YD	SQ YD	TON	SQ YD	PCC TON	MILL TON	BINDER TON	TON	TON
US 34													
LT. STA. 425+39 - 425+87						33.4		33.4					
RT. STA. 425+39 - 425+82						45.8		45.8					
STA. 426+30.1 TO 426+59.1		88.8	88.8			88.8			0.02		0.01	5.0	7.7
LT. STA. 428+16 TO 432+16					225.13		50.7	225.1					
STA. 12+58 - 432+16		606.9	606.9			606.9			0.12		0.07	34.0	52.8
6TH STREET													
LT. AND RT. STA. 8+53.8 TO 9+56 (MAINLINE E.O.P.)										0.38	0.11	53.6	83.3
LT. AND RT. STA. 11+64.2 (MAINLINE E.O.P.) TO 10+44.2										0.42	0.13	58.5	90.9
LT. STA. 8+69.8 - STA. 425+03.9	148.0		148.0			148.0			0.03		0.02	8.3	12.9
STA. 425+39.7 - RT. STA. 11+64.2	95.2		95.2			95.2			0.02		0.01	5.3	8.3
SW ISLAND					33.54								
NW ISLAND					36.01								
RT. STA. 12+09				97.3	97.31								
SUB-TOTAL									0.19	0.80	0.35		
TOTAL	243.1	695.7	938.8	97.3	392.0	1018.0	51	304.3		1.3		165	256

NOTE: A UNIT OF 116 LBS PER SQ. YD. WAS USED FOR SURFACE MIX "E" CALCULATIONS AND 112 LBS PER SQ. YD. USED FOR ALL OTHER MIXES.

42400100 - PORTLAND CEMENT
CONCRETE SIDEWALK 4"

LOCATION	SQ FT
6TH STREET	
LT. STA. 7+29.4 TO 9+22.0	567.8
LT. STA. 10+84.0 TO 11+36	418.5
TOTAL	986.3

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF
QUANTITIES
PROPOSED ITEMS

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY