CONT.	*68356				
FEO. RO	AD DIST. NO. 4	ILLINOIS	FED. A	D PROJECT	
STA.		TO	STA.		
313	1031-3		WARREN		4
F.A.P.	SECTION	COUNTY		TOTAL SHEETS	SHE

US 34 & SIXTH ST. SCHEDULE OF QUANTITIES						
ITEM DESCRIPTION	UNIT	QTY				
CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	230				
CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	114				
CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	109				
CONDUIT PUSHED, 3 1/2" DIA., PVC	FOOT	313				
CONCRETE HANDHOLE	EACH	3				
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	497				
ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 1/C NO. 6	FOOT	802				
LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	2				
ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	535.5				
ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	3843				
TRAFFIC SIGNAL POST, GALVANIZED STEEL, 15 FT.	EACH	1				
STEEL MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	1				
STEEL MAST ARM ASSEMBLY AND POLE 50 FT.	EACH	1				
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT.	EACH	2				
CONCRETE FOUNDATION, TYPE A	FOOT	3				
CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	50				
DRILL EXISTING HANDHOLE	EACH	5				
TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	10				
PEDESTRIAN PUSH-BUTTON	EACH	2				
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1				
REMOVE EXISTING HANDHOLE	EACH	8				
REMOVE EXISTING CONCRETE FOUNDATION	EACH	4				
VIDEO VEHICLE DETECTION SYSTEM, 4 CAMERA	EACH	1				
ELECTRIC CABLE IN CONDUIT, 1/C, NO. 6 GROUNDING	FOOT	636.5				
SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	10				
SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	. 6				
PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	2				
REMOVE AND REINSTALL FIBER OPTIC CABLE IN CONDUIT	LSUM	1				
NDUCTIVE LOOP DETECTOR	EACH	4				
BATTERY BACKUP SYSTEM WITH CABINET	EACH	1				
FULL-ACTUATED CONTROLLER IN EXISTING CABINET, SPECIAL	EACH	1				

REVISIONS		ILLINOIS DEPARTM	ENT OF TRANSPORTATION	
NAME	DATE	ILLINOIS DEPARTMENT OF TRANSPORTATION		
		SCHEDULE (OF QUAN	TITIES
		TRAFFI	C SIGNA	\LS
~~~~~~~~~~~		US 3	4 & SIX	TH
······		HTUOMNOM	WARREN	COUNTY
		SCALE: VERT. HORIZ.	D	RAWN BY
		DATE	С	HECKED BY