

68379

F.A.S. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
380		KNOX	35	4

## SUMMARY OF QUANTITIES

100% STATE

CODE NO.	PAY ITEM	UNIT	Y007 TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	459
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	123
20200100	EARTH EXCAVATION	CU YD	1,013
20400800	FURNISHED EXCAVATION	CU YD	466
20800150	TRENCH BACKFILL	CU YD	13
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3,858
* 25000200	SEEDING, CLASS 2	ACRE	0.8
* 25000400	NITROGEN FERTILIZER NUTRIENTS	POUND	72
* 25000500	PHOSPHORUS FERTILIZER NUTRIENTS	POUND	72
* 25000600	POTASSIUM FERTILIZER NUTRIENTS	POUND	72
* 25100115	MULCH, METHOD 2	ACRE	0.8
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	80
28000300	TEMPORARY DITCH CHECKS	EACH	10
28000400	PERIMETER EROSION BARRIER	FOOT	410
28100107	STONE RIPRAP, CLASS A4	SQ YD	140
28100125	STONE RIPRAP, CLASS B3	SQ YD	229
28200200	FILTER FABRIC	SQ YD	140
44200144	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	14
48101200	AGGREGATE SHOULDERS, TYPE B	TON	81
50102400	CONCRETE REMOVAL	CU YD	16
50105200	REMOVE EXISTING CULVERTS	EACH	1
50800105	REINFORCEMENT BARS	POUND	3,641
54002020	EXPANSION BOLTS 3/4 INCH	EACH	36

CODE NO.	PAY ITEM	UNIT	Y007 TOTAL QUANTITY
54003000	CONCRETE BOX CULVERTS	CU YD	12
54201273	PIPE CULVERTS, TYPE 2 RCCP 18"	FOOT	48
54201285	PIPE CULVERTS, TYPE 2 RCCP 30"	FOOT	66
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	4
54248500	CONCRETE HEADWALLS	CU YD	5.9
54248510	CONCRETE COLLAR	CU YD	4.1
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
63200310	GUARDRAIL REMOVAL	FOOT	950
66600105	FURNISH AND ERECT RIGHT OF WAY MARKERS	EACH	27
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
* A2001216	TREE, ACER RUBRUM RED SUNSET (RED SUNSET RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	5
* A2002816	TREE, CATALPA SPECIOSA (NORTHERN CATALPA), 2" CALIPER, BALLED AND BURLAPPED	EACH	5
* A2006916	TREE, QUERCUS PALUSTRIS (PIN OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	5
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.0
Z0022800	FENCE REMOVAL	FOOT	1,334
Z0073100	TEMPORARY SHORING	EACH	2

\* SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

### SUMMARY OF QUANTITIES