

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
404		PEORIA	27	4
STA. 459+08.81		TO STA. 460+84.25		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		
• 04 Joint Repair 2006				

SCHEDULE OF QUANTITIES

MOBILIZATION

ENTIRE PROJECT = 1.0 LSUM

T, C, & P, STANDARD 701201

QUEENWOOD JOBSITE = 1.0 LSUM

T, C, & P, STANDARD 701406

INDIAN CRK. JOBSITE = 1.0 LSUM

T, C, & P, STANDARD 701601

BARTONVILLE JOBSITE = 0.5 LSUM
 122E JOBSITE = 0.5 LSUM
1.0 LSUM

BLAST CLEANING BRIDGE JOINT STEEL

BRIDGE JOBSITES = 1078 FOOT

METALIZING BRIDGE JOINT STEEL

BRIDGE JOBSITES = 972 FOOT

SILICONE JOINT SEALER

BRIDGE JOBSITES = 1078 FOOT

BRIDGE MEDIAN EPDM SPECIAL

BARTONVILLE JOBSITE = 890 FOOT

BITUMINOUS REMOVAL (MISCELLANEOUS)

IL. 122E BRIDGE JOBSITE = 8.0 SQ. YD.

BITUMINOUS MIXTURE FOR PATCHING

IL. 122E BRIDGE JOBSITE = 1.0 TON

BLAST CLEANING PPC BEAM ENDS

INDIAN CREEK BRIDGE JOBSITE = 48 FOOT

METALIZING PPC BEAM ENDS

INDIAN CREEK BRIDGE JOBSITE = 279 SQ. FT.

PLAT DATE
 PLOT SCALE
 PLOT SCALE
 REFERENCE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
 HORIZ.
 DATE 01-13-2004

DRAWN BY: CEJ
 CHECKED BY: