| RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| * | RS, R | ** | 302 | 3 |
| FED. ROAD DIST. NO. 6 | ILLINOIS | FED. AID PROJECT | | |

* FAU 8239, FAS 1767, FAS 1766 & SBI 16 (OLD US 66)
** MONTGOMERY & MACOUPIN COUNTIES

**CONTRACT NO. 72526**

| CODED NO | SUMMARY OF QUANTITIES ITEM | UNIT | TOTAL QUANTITY 80% FEDERAL 20% STATE | CONSTRUCTION CODE — MONTGOMERY COUNTY: TRAFFIC SIGNALS FAU 8239 - URBAN OLD US 66 & IL ROUTE 16 Y031-1F | MONTGOMERY COUNTY: ROADWAY FAU 8239 - URBAN BITUMINOUS RESURFACING NORTH PROJECT LIMITS TO STA 688+28.13 BK NB & SB STA 688+48.07 AH TO STA 690+15.7 NB & SB STA 690+15.7 TO STA 780+75.59 SB STA 750+19.70 TO STA 780+75.59 NB IL RTE 16 STA 922+02.0 TO STA 924+67.0 I000-2A | MONTGOMERY COUNTY: ROADWAY FAU 8239 - URBAN PORTLAND CEMENT CONCRETE RECONSTRUCTION STA 690+15.7 TO STA 750+20.0 NB J000-2A | MONTGOMERY COUNTY: ROADWAY FAS 1767 - RURAL BITUMINOUS RESURFACING STA 780+75.59 TO STA 842+76.49 BK STA 843+89.12 AH TO STA 981+68.70 I000-2A | MACOUPIN COUNTY: ROADWAY FAS 1766 - RURAL BITUMINOUS RESURFACING STA 981+68.70 TO STA 1010+89.70 BK STA 1025+03.03 AH TO STA 1297+00.00 BK STA 50+00.00 AH TO STA 76+72.05 BK STA 109+00.00 AH TO STA 120+90.00 IL RTE 138 - STA 112+63.04 TO STA 124+47.17 I000-2A | MACOUPIN COUNTY: ROADWAY SBI 16 - RURAL BITUMINOUS RESURFACING STA 60+90.71 TO STA 40+00 BK STA 1136+96.28 AH TO STA 1176+35.97 BK STA 70+00.00 AH TO STA 64+53.12 I000-2A | MACOUPIN COUNTY: TRAFFIC SIGNALS FAS 1766 - RURAL OLD US 66 & IL ROUTE 138 Y031-1F |
|---|---|---|---|---|---|---|---|---|---|---|
| 20100110 | TREE REMOVAL (6-15 UNITS DIAMETER) | UNIT | 18 | | | | | | 18 | |
| 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER) | UNIT | 20 | | | | | 20 | | |
| 20200100 | EARTH EXCAVATION | CU YD | 1402 | | | | | 1402 | | |
| 20200500 | EARTH EXCAVATION (WIDENING) | CU YD | 1261 | | | | | 1202 | | |
| ~~20100800~~ | ~~FURNISHED EXCAVATION~~ | ~~CU YD~~ | ~~500~~ | | | | 59 14 | 486 | | |
| 20800150 | TRENCH BACKFILL | CU YD | 39 | | 1 | 6 | | 28 | 4 | |
| 21400100 | GRADING AND SHAPING DITCHES | FOOT | 21,555 | | 3,087 | 300 | 6,037 | 3,813 | 8,318 | |
| 25000200 | SEEDING, CLASS 2 | ACRE | 15.75 | | 2.25 | 0.25 | 4.25 | 4.50 | 4.50 | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 1,489 | | 194 | 24 | 391 | 466 | 414 | |
| 25000500 | PHOSPHOROUS FERTILIZER NUTRIENT | POUND | 1,489 | | 194 | 24 | 391 | 466 | 414 | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 1,489 | | 194 | 24 | 391 | 466 | 414 | |
| 25000700 | AGRICULTURAL GROUND LIMESTONE | TON | 33.1 | | 4.3 | 0.5 | 8.7 | 10.4 | 9.2 | |
| 25002024 | SEEDING, CLASS 4B (MODIFIED) | ACRE | 1.00 | | | | 0.25 | 0.75 | | |
| 25100115 | MULCH, METHOD 2 | ACRE | 16.75 | | 2.25 | 0.25 | 4.50 | 5.25 | 4.50 | |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 238 | | | | | 238 | | |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 5,025 | | 675 | 75 | 1,350 | 1,575 | 1,350 | |
| 28000300 | TEMPORARY DITCH CHECKS | EACH | 85 | | 10 | 4 | 8 | 28 | 35 | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 2,234 | | 104 | | | 2,130 | | |
| 28000500 | INLET AND PIPE PROTECTION | EACH | 53 | | 12 | | 9 | 13 | 19 | |
| 28100208 | STONE RIPRAP, CLASS A4 (SPECIAL) | TON | 67 | | | | | 67 | | |
| 28100707 | STONE DUMPED RIPRAP, CLASS A4 | SQ YD | 516 | | | | | 516 | | |
| 28200200 | FILTER FABRIC | SQ YD | 516 | | | | | 516 | | |
| 30200650 | PROCESSING MODIFIED SOIL 12" | SQ YD | 18,283 | | | 18,283 | | | | |
| 30201500 | LIME | TON | 292.5 | | | 292.5 | | | | |
| 31200100 | STABILIZED SUB-BASE, 4" | SQ YD | 17,642 | | | 17,642 | | | | |
| 35800100 | PREPARATION OF BASE | SQ YD | 242 | | | | 242 | | | |
| 40200800 | AGGREGATE SURFACE COURSE, TYPE B | TON | 53 | | 2 | | 5 | 35 | 11 | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 179.2 | | 28.8 | 0.5 | 48.4 | 87.6 | 13.9 | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 944 | | 152 | 2 | 255 | 461 | 74 | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | | | | | 2 | | |
| 40600980 | BITUMINOUS SURFACE REMOVAL - BUTT JOINT | SQ YD | 5,563 | | 1,197 | 591 | 610 | 2,504 | 661 | |
| 40600985 | PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT | SQ YD | 2,537 | | | | 609 | 1,760 | 168 | |
| 40600990 | TEMPORARY RAMP | SQ YD | 1,821 | | 892 | 64 | 156 | 628 | 81 | |
| 40800040 | INCIDENTAL BITUMINOUS SURFACING | TON | 447 | | 3 | | 119 | 206 | 119 | |
| 42000411 | PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED) | SQ YD | 16,362 | | | 16,362 | | | | |
| 42001300 | PROTECTIVE COAT | SQ YD | 17,995 | | | 16,362 | | 1,633 | | |

| REVISIONS NAME | DATE |
|---|---|
| | |

Rev. 4-18-06

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.
DATE 2/8/2006

DRAWN BY TJD
CHECKED BY AWM

2280-10001