

F.A.I. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55 (84-4(B)-I)I	SANGAMON	9	3
STA. TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	

URBAN

PAY CODES	ITEMS	UNITS	TOTAL	DE MISC
				100% STATE
				1000
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2
60260100	INLETS TO BE ADJUSTED	EACH	8	8
67100100	MOBILIZATION	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1	1
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	84	84
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	84	84
M4060085	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ M	1003	1003
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	7.6	7.6
M4060300	AGGREGATE (PRIME COAT)	M TON	20.3	20.3
M4060990	TEMPORARY RAMP	SQ M	134	134
M4402700	PORTLAND CEMENT CONCRETE REMOVAL (VARIABLE DEPTH)	SQ M	8237	8237
M7800410	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B- LINE 125MM	METER	1263	1263
MX032077	POLYMER CONCRETE	CU M	1.2	1.2
MX406058	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N105	M TON	1082	1082
MX406M60	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N105	M TON	676	676

\* SPECIALTY ITEMS

PLOT DATE = 1/23/2008  
 FILE NAME = c:\projects\0553886\app\pr2.dgn  
 PLOT SCALE = 1/8" = 1' IN.  
 USER NAME = baw

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAI 55  
 SECTION (84-4(B)-I)I  
 SANGAMON COUNTY

SCALE: VERT.  
 DATE:       HORIZ.

DRAWN BY  
 CHECKED BY