

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
121	134RS-4	LOGAN	67	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

ENTRANCE IMPROVEMENT SCHEDULE FOR OLD IL 121

APPROX. LOCATION	LT/RT	TYPE OF ENTRANCE (SR/PE/CE/MB)	EX. MATERIAL TYPE (AGG./PCC/BIT)	WIDTH AT BACK	AREA CE/PE/SR	AREA MB	AGGREGATE SURF. TY B	INC. BIT. SURF. CSE.	BIT MATLS (PRIME COAT)	AGGREGATE (PRIME COAT)	PREP OF BASE	AGG BASE REPAIR
				FEET	SO YD	SO YD	TON	TON	TON	TON	SO YD	TON
346+69.6	LT	PE	AGG.	14	32.00		1.24	3.83	0.01	0.05	19.56	0.84
351+09.5	LT	PE	AGG.	26	53.33		2.30	5.92	0.02	0.08	30.22	1.29
360+60.2	LT	PE	AGG.	16	35.56		1.42	4.18	0.01	0.04	21.33	0.91
363+17.4	LT	PE	AGG.	21	44.44		1.86	5.05	0.01	0.09	25.78	1.10
363+88.2	LT	PE	AGG.	13	30.22		1.15	3.66	0.01	0.08	18.67	0.80
364+84.9	LT	PE	AGG.	14	32.00		1.24	3.83	0.03	0.08	19.56	0.84
369+83.3	RT	PE	BIT.	16	21.33		3.58	3.58	0.01	0.04		
372+86.5	RT	PE	BIT.	72	71.11		6.38	11.95	0.03	0.14		
376+35.00	LT	CE.	AGG.	35	69.33		3.10	7.49	0.07	0.10	38.22	1.63
376+35.00	LT	CE.	AGG.	35	69.33		3.10	7.49	0.07	0.10	38.22	1.63
379+24.6	RT	PE	BIT.	17	30.00		1.51	2.52	0.01	0.06		
379+52.3	LT	PE	BIT.	27	41.11		2.39	3.45	0.02	0.08		
379+55.7	RT	PE	BIT.	11	16.89		2.84	2.84	0.03	0.05		
380+39.6	LT	PE	AGG.	13	30.22		1.15	3.66	0.01	0.05	18.67	0.80
381+47.3	LT	PE	AGG.	13	30.22		1.15	3.66	0.01	0.05	18.67	0.80
382+36.82	LT	PE	AGG.	18	39.11		1.59	4.53	0.01	0.06	23.11	0.99
383+00.00	LT	PE	AGG.	19	40.89		1.68	4.70	0.01	0.06	24.00	1.03
383+13.57	RT	PE	BIT.	19	40.89		1.68	4.70	0.01	0.06		
383+56.13	LT	PE	AGG.	19	40.89		1.68	4.70	0.01	0.06	24.00	1.03
383+95.1	RT	PE	BIT.	12	17.78		2.99	2.99	0.03	0.05		
384+16.7	LT	PE	AGG.	12	28.44		1.06	3.48	0.01	0.05	17.78	0.76
384+83.8	LT	PE	AGG.	14	32.00		1.24	3.83	0.01	0.05	19.56	0.84
385+19.60	LT	CE.	AGG.	35	69.33		3.10	7.49	0.07	0.10	38.22	1.63
385+72.55	LT	CE.	AGG.	35	69.33		3.10	7.49	0.07	0.10	38.22	1.63
386+97.5	LT	PE	AGG.	14	32.00		1.24	3.83	0.05	0.05	19.56	0.84
387+66.8	RT	PE	Earth	39	76.44		3.45	8.19	0.02	0.08	41.78	1.78
388+24.2	LT	PE	AGG.	26	53.33		2.30	5.92	0.02	0.10	30.22	1.29
393+95.	LT	PE/MB	BIT.	25	51.56	20.44	2.21	9.76	0.04	0.10		
396+96.8	LT	PE/MB	BIT.	22	46.22	20.44	1.95	9.23	0.05	0.09		
398+46.	LT	PE	BIT.	47	48.89		8.21	8.21	0.02	0.14		
399+46.1	LT	FE	Earth	18	39.11		1.59	4.53	0.06	0.09	23.11	0.99
ENTRANCE TOTALS					1333.33	40.89	73.52	166.73	0.86	2.37	548.44	23.42

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES

SCALE: VERT. / HORIZ. DATE
DRAWN BY: BDK
CHECKED BY: BDK