

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
121	134RS-4	LOGAN	67	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SIDE ROAD IMPROVEMENT SCHEDULE FOR IL 121

APPROX. LOCATION	LT/RT	TYPE OF ENTRANCE	STREET NAME	EX. MATERIAL TYPE	LENGTH AT BACK	AREA CE/PE /SR	PR. BIT. CONC THICKNESS	BIT. SURF. REMOVAL - BUTT JOINT	INC. BIT. SURF. CSE.	BIT MATLS (PRIME COAT)	AGGREGATE (PRIME COAT)
		(SR/PE/CE/MB)		(AGG./PCC/BIT.)							
					FEET	SO YD	IN	SO. YD.	TON	TON	TON
359+86.2	RT	SR	350 ST.	BIT.	92	113.33	3" to 1.5"	113.33	14.28	0.04	0.23
365+80.3	RT	SR	Huston ST.	BIT.	22	35.56	3" to 1.5"	35.56	4.48	0.01	0.07
368+68.3	RT	SR	HennST.	BIT.	27	41.11	3" to 1.5"	41.11	5.18	0.02	0.08
371+55.0	RT	SR	Howe ST.	BIT.	33	47.78	3" to 1.5"	47.78	6.02	0.02	0.10
375+05.9	RT	SR	Walnut ST.	BIT.	27	41.11	3" to 1.5"	41.11	5.18	0.02	0.08
378+13.0	RT	SR	Main ST.	BIT.	37	52.22	3" to 1.5"	52.22	6.58	0.02	0.10
378+13.2	LT	SR	Main ST.	BIT	35	50.00	3" to 1.5"	50.00	6.30	0.02	0.10
38126.9	RT	SR	Macon ST.	BIT	50	66.67	3" to 1.5"	66.67	8.40	0.03	0.13
385+08.4	RT	SR	Joynt ST.	BIT	50	66.67	3" to 1.5"	66.67	8.40	0.03	0.13
394+71.3	RT	SR	Olive ST.	BIT	59	76.67	3" to 1.5"	76.67	9.66	0.03	0.15
SUB-TOTAL SIDEROADS								591.11	74.48	0.22	1.18
ENTRANCE TOTALS								0.00	166.73	0.86	2.37
GRAND TOTALS								591.11	241.21	1.08	3.55

PLOT DATE : 2/16/2006  
 FILE NAME : c:\puro\proj\14828286\shs\shs\shs\shs.dwg  
 PLOT SCALE : 1/8"=1'-0"  
 USER NAME : brenthume

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 SCALE: VERT. DATE  
 HORIZ.  
 DRAWN BY: BDK  
 CHECKED BY: BDK