

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
121	134RS-4	LOGAN	67	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

BINDER SCHEDULE (ADDITIONAL BINDER TO BUILD SUPER) - OLD IL 121							
LOCATION STATION TO STATION		LT/RT	RD WIDTH LT + RT		LENGTH	ROAD AREA	BIT CONC LEVEL BINDER SUPER N50 VARIABLE
						SO YD	TON
344+78.01	346+24.88	LT	11	LT	146.875	179.51	10.05
346+24.88	349+94.49	LT/RT	11	LT	369.604	451.74	50.59
349+94.49	351+41.36	RT	11	RT	146.875	179.51	15.08
355+52.05	357+17.26	LT	9	LT	165.217	165.22	27.76
357+17.26	362+84.21	LT/RT	9	LT	566.944	566.94	190.49
362+84.21	364+49.42	LT	9	LT	165.217	165.22	55.51
TOTALS						1708.14	349.49

TEMPORARY RAMP SCHEDULE			
APPROX. LOCATION	WIDTH FT	STREET NAME	TEMP RAMP SO. YD
6+31.03	25	350th ST	5.56
6+31.03	25	HUSTON ST	5.56
9+40.70	25	WALNUT ST	5.56
9+40.70	25	MAIN ST	5.56
9+63.51	25	MAIN ST	13.89
9+72.48	25	MACON ST	13.89
12+19.00	25	JOYNT ST	5.56
12+25.20	25	OLIVE ST	5.56
TOTAL			61.11

BIT SHOULDER, 8"					
LOCATION STATION TO STATION		LT/RT	SHLDR WIDTH	LENGTH	SHLDR AREA
					SO YD
344+01.780	344+63.946	RT	4	118	52.44
344+01.780	344+77.326	LT	4	92	40.89
400+41.884	401+29.720	RT	4	118	52.44
400+43.005	401+29.720	LT	4	95	42.22
TOTALS				423	188.00

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 VERT. SCALE: _____
 HORIZ. SCALE: _____
 DATE: _____
 DRAWN BY: BDK
 CHECKED BY: BDK