

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1808	(1)RS-2	LAWRENCE	15	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		1000 100% STATE	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	215	215	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7334	7334	
40600300	AGGREGATE (PRIME COAT)	TON	147	147	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	733	733	
40600990	TEMPORARY RAMP	SQ YD	589	589	
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	5040	5040	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	68301	68301	
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SQ YD	270	270	
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	586	586	
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	51	51	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2082	2082	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8891	8891	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	68000	68000	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	19	19	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	988	988	
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	68000	68000	
*78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	19	19	
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	367	367	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	6161	6161	
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	36	36	

* SPECIALTY ITEMS

PLOT DATE = 10/19/2008
 FILE NAME = c:\projects\74058\48388.dgn
 PLOT SCALE = ASCALE
 USER NAME = steffanmk

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE