F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	27-1R	ST. CLAIR	382	75
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 76300

PRE - STAGE 1 AND STAGE 1

TEMPORARY PAVEMENT MARKINGS

STATION	TO STATION	ALIGNMENT	SIDE	TEMP PVMT MARKING LINE 4" WHITE FOOT	TEMP PVMT MARKING LINE 4" YELLOW FOOT	TEMP PVMT MARKING LINE 8" WHITE FOOT	TEMP PVMT MARKING LINE 12" WHITE FOOT	TEMP PVMT MARKING LINE 12" YELLOW FOOT	TEMP PVMT MARKING LINE 24" WHITE FOOT	TEMP PVMT MARKING L & S SQ FT	REMARKS
148+85	150+10	FAP 103	LT	190							2 WHITE LANE LINES (PRE-STAGE)
148+85		FAP 103	LT						50		STOP BARS (PRE-STAGE)
150+10	151+50	FAP 103	LT	35							WHITE DOTTED (PRE-STAGE)
148+85	161+00	FAP 103	LT		1215						YELLOW EDGE LINE (PRE-STAGE)
161+00	162+25	FAP 103	LT		250						DOUBLE YELLOW (PRE-STAGE)
147+90	149+10	FAP 103	RT				156				2 ISLANDS (PRE-STAGE)
138+40	148+20	FAP 103	RT	980							WHITE EDGE LINE(PRE-STAGE)
145+00	148+20	FAP 103	RT	320							WHITE LANE LINE (PRE-STAGE)
148+20		FAP 103	RT						24		STOP BARS (PRE-STAGE)
145+50	148+00	FAP 103	RT							54.4	4 LEFT TURN ARROWS (PRE-STAGE)
149+00	161+00	FAP 103	RT		1200						YELLOW EDGE LINE (PRE-STAGE)
148+85	158+50	FAP 103	RT		965						YELLOW EDGE LINE (STAGE 1)
158+50	161+00	FAP 103	CL		250						YELLOW CENTERLINE (STAGE 1)
149+00	161+00	FAP 103	RT	1200							WHITE EDGE LINE (STAGE 1)
161+00	162+25	FAP 103	CL		31						YELLOW SKIP-DASH (STAGE 1)
TOTALS (RURAL)				2725	3911		156		74	54.4	

PRE - STAGE 1 AND STAGE 1

PAVEMENT MARKING REMOVAL

STATION	TO STATION	ALIGNMENT	SIDE	PAVEMENT MARKING REMOVAL SQ FT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	REMARKS
150+10	151+50	F.A.P. 103	LT.	47		WHITE LANE LINE (PRE-STAGE 1)
149+50	151+50	F.A.P. 103	LT.	17		WHITE SKIP-DASH (PRE-STAGE 1)
148+20	-	F.A.P. 103	RT.	24		PART STOP BAR (PRE-STAGE 1)
138+40	148+20	F.A.P. 103	RT.	82		WHITE SKIP-DASH (PRE-STAGE 1)
148+85	150+00	F.A.P. 103	RT.	10		WHITE SKIP-DASH (PRE-STAGE 1)
158+50	161+00	F.A.P. 103	CL	83		YELOW EDGE LINE (PRE-STAGE 1)
158+50	161+00	F.A.P. 103	CL		83	YELLOW EDGE LINE (STAGE 1)
161+00	162+25	F.A.P. 103	CL		84	DOUBLE YELLOW (STAGE 1)
148+85	153+00	F.A.P. 103	CL	138		YELLOW EDGE LINE (STAGE 1)
TOTALS (RURAL)				401	167	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL - STAGE 1 SCHEDULE

F.A.P. 103 (IL. RTE. 13/15)
SECTION 27-1R - ST. CLAIR CO.

SCALE: DRAWN BY CRO

DATE Febuary 11, 2005 CHECKED BY RCY

J:\2002\02058\000\civil\dgn\traffic_control_schedule_stage_1.dgn 3/9/2005 9:48:PM