

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	ST. CLAIR	101	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* FAU 9251 / FAS 1848				
** 28-3BR-1, 28-4BR				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT		28-3BR-I I000-2A	28-3BR-I X071-2A	SFTY-3N	28-4BR I000-2A	28-4BR X071-2A	SFTY-3N		
50300260	BRIDGE DECK GROOVING	SQ YD	1165		705			460			
50300300	PROTECTIVE COAT	SQ YD	1428.5		852			576.5			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		0.61			0.39			
50500505	STUD SHEAR CONNECTORS	EACH	5430		3120			2310			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	119,710		70570			49140			
51201400	FURNISHING STEEL PILES HP10X42	FOOT	801		801						
51201700	FURNISHING STEEL PILES HP12X74	FOOT	1540					1540			
X0325278	DRIVING STEEL PILES	FOOT	1429		389			1540			
51203400	TEST PILE STEEL HP10X42	EACH	1		1						
X0325277	PILE SHOES	EACH	28					28			
51205200	TEMPORARY SHEET PILING	SQ FT	1958		1958						
51500100	NAME PLATES	EACH	2		1			1			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	136		73			63			
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	311		171			140			
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	375	200			175				
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1				1				
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	4			4				
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	7	4			3				
63200310	GUARDRAIL REMOVAL	FOOT	1675	987.5			687.5				
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	412.5	225			187.5				
63301990	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	4	2			2				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	19		12			7			
67100100	MOBILIZATION	L SUM	1		0.61			0.39			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5			0.5				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5			0.5				
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	2		1			1			
70106600	TEMPORARY BRIDGE TRAFFIC SIGNALS (STATE FURNISHED CONTROLLER)	EACH	2		1			1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	232	152			80				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	31	31							
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6998	5000			1998				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1863	1125			738				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	212	212							

*SPECIALTY ITEMS

PLOT DATE = 2/8/2006
 FILE NAME = c:\pcc\pcc\ad12400\pcc\pcc\pcc.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 REFERENCE = REF#