

# SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	ST. CLAIR	101	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* FAU 9251 / FAS 1848				
** 28-3BR-I, 28-4BR				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT		28-3BR-I 1000-2A	28-3BR-I X071-2A	SFTY-3N	28-4BR 1000-2A	28-4BR X071-2A	SFTY-3N		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2653	1960			693				
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	987.5	612.5			375				
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	875	512.5			362.5				
70500100	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	412.5	225			187.5				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	31	31							
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5429	3809			1620				
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	109	109							
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1566	1188			378				
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	103	103							
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	48	41			7				
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	12		10			2			
78100300	REPLACEMENT REFLECTOR	EACH	7	5			2				
78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	9			7				
78200520	BARRIER WALL MARKERS, TYPE B	EACH	6		3			3			
78200530	BARRIER WALL MARKERS, TYPE C	EACH	6		3			3			
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	7	4			3				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2576	1910			666				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	67	56			11				
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	456					456			
X3550610	BITUMINOUS BASE COURSE SUPERPAVE 9 1/2"	SQ YD	633	338			295				
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	341	211			130				
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - L1	EACH	1					1			
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	1753	1291			462				
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - L2	EACH	1								
X5020503	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 3	EACH	1		1						
X5020504	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 4	EACH	1		1						
X7200200	WIDE LOAD SIGNING	L SUM	1	0.5			0.5				
Z0002600	BAR SPLICERS	EACH	1111		611			500			
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4			2				2	
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1							1	

PLOT DATE = 3/1/2006  
 FILE NAME = c:\pwork\msh\ed2480\plan\pin0514.dgn  
 PLOT SCALE = 80.0000 / IN.  
 REFERENCE = #REF#

\* SPECIALTY ITEMS

Rev.