


SUMMARY OF QUANTITIES

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 OR "CUAN" (CHICAGO UTILITY ALERT NETWORK), 312-744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
- THE CONTRACTOR SHALL CORDINATE CONSTRUCTION ACTIVITES WITH UTILITY COMPANIES AND THE VILLAGE
- BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE USED- ONE (1) WEIGHTED SANDBAG ACROSS EACH BOTTOM RAIL

SCHEDULE OF PRICES OGDEN AVENUE STREET SIGN MODERNIZATION ALTERNATE 1

CODE NO.	ITEM NO.	ITEM DESCRIPTION	UNIT	QUAN.
XX006385	1	SIGN PANEL AND POST REMOVAL (TYPE 1)	EACH	57
72400320	2	REMOVE SIGN PANEL-TYPE 2	SQ FT	115
XX006386	3	SIGN PANEL AND APPURTENANCES - TYPE 1	SQ FT	587
XX006387	4	SIGN PANEL AND APPURTENANCES - TYPE 2	SQ FT	135
XX006388	5	FLUTED SIGN SUPPORT	EACH	57
XX006389	6	18" DIA. DRILLED SHAFT CONCRETE FOUNDATION	EACH	57
70102622	7	2L,2W, WITH BI-DIRECTIONAL LEFT TURN LANE, STANDARD 701502	L.S.	1
70102640	8	LANE CLOSURE MULTILANE, 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE STANDARD 701801.	L.S.	1
70102635	9	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L.S.	1
67100100	10	MOBILIZATION	L.S.	1

 ENGINEERING DEPARTMENT	OGDEN AVENUE STREET SIGN MODERNIZATION QUANTITIES		REVISIONS	
	DATE: 1/14/05	PROJECT NO. #18-04	NAME	DATE
	REVISION: 7/18/05	SHEET 2 OF 6		
	DRAWN BY: RWB		CHECKED BY: D.J.G.	
	FILE NAME: C:\CADFILES\OGDEN AVE\QUANTITIES			