

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1 - 1	ROCK ISLAND	239	5
STA. 75+60.93		TO STA. 116+00.00		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		CONTRACT # 84986

← URBAN →

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITIES	2 - LANE 75+61 - 86+07		4 - LANE 86+07 - 116+00		90% STATE 10% CITY Y031 - 1F	100% CITY OF ROCK ISLAND Y060	50% STATE 50% CITY SFTY-1B
				100% STATE I000 - 2A	100% STATE I000 - 2A	100% STATE I000 - 2A	100% STATE I000 - 2A			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	136			136				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	575	36		539				
20100500	TREE REMOVAL, ACRES	ACRE	2.00	1.00		1.00				
20200100	EARTH EXCAVATION	CU YD	34425	9000		25425				
20800150	TRENCH BACKFILL	CU YD	1,737	354		1383				
20900110	POROUS GRANULAR BACKFILL	CU YD	12	12						
21001000	GEO TECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	31916	6474		25442				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	26757	5773		20984				
25000400 *	NITROGEN FERTILIZER NUTRIENT	POUND	472	125		347				
25000500 *	PHOSPHORUS FERTILIZER NUTRIENT	POUND	472	125		347				
25000600 *	POTASSIUM FERTILIZER NUTRIENT	POUND	472	125		347				
25000910 *	SEEDING, CLASS 1 (MODIFIED)	ACRE	4.75	0.25		4.50				
25100115 *	MULCH, METHOD 2	ACRE	4.75	0.25		4.50				
25100630	EROSION CONTROL BLANKET	SQ YD	2797	564		2233				
25200100 *	SODDING	SQ YD	14483	3323		11160				
25200200	SUPPLEMENTAL WATERING	UNIT	130.4	28.5		101.9				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1200	300		900				
28000300	TEMPORARY DITCH CHECKS	EACH	18			18				
28000400	PERIMETER EROSION BARRIER	FOOT	2185	570		1615				
28000500	INLET AND PIPE PROTECTION	EACH	68	18		50				
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	155	11		144				
28200200	FILTER FABRIC	SQ YD	155	11		144				
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	28638	5902		22736				
35101400	AGGREGATE BASE COURSE, TYPE B	TON	2826	297		2529				
35500100	BITUMINOUS BASE COURSE 4"	SQ YD	359			359				
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	669	243		426				
40500300	BITUMINOUS MIXTURE COMPLETE	TON	535	140		395				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.0	2.2		2.8				
40600895	CONSTRUCTING TEST STRIP	EACH	2	1		1				
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	1235	112		1123				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	18578						18578	
42400800	DETECTABLE WARNINGS	SQ FT	140	20		120				
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	9556	2508		7048				
44000100	PAVEMENT REMOVAL	SQ YD	15805	3802		12003				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1196	72		1124				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3145	1004		2141				
44002805	ISLAND REMOVAL	SQ FT	626			626				
50100300 *	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1				
50100400 *	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1				
50100500 *	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1			1				

* SPECIALTY ITEM

SUMMARY OF QUANTITIES