

SUMMARY OF QUANTITIES

← URBAN →

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
599	1 - 1	ROCK ISLAND	239	#
STA. 75+60.93		TO STA. 116+00.00		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT # 84986				

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITIES	2 - LANE 75+61 - 86+07	4 - LANE 86+07 - 116+00	90% STATE 10% CITY Y031 - 1F	100% CITY OF ROCK ISLAND Y060	50% STATE 50% CITY SFTY-1B
				100% STATE I000 - 2A	100% STATE I000 - 2A			
50200100	STRUCTURE EXCAVATION	CU YD	699	592	107			
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	193	193				
50300225	CONCRETE STRUCTURES	CU YD	570.5	354.5	216.0			
50300300	PROTECTIVE COAT	SQ YD	471	394	77			
50500505	STUD SHEAR CONNECTORS	EACH	2310	818	1492			
50700209	UNTREATED TIMBER LAGGING	SQ FT	12354	8084	4270			
50700215	FURNISHING SOLDIER PILES (W SECTION)	FOOT	3990	3011	979			
50800105	REINFORCEMENT BARS	POUND	40		40			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	76120	47400	28720			
50900805	PEDESTRIAN RAILING	FOOT	1106	933	173			
51205200	TEMPORARY SHEET PILING	SQ FT	104		104			
50700213	FURNISHING SOLDIER PILES (BUILD-UP SECTIONS)	FOOT	656		656			
54002070	EXPANSION BOLTS 3/4 INCH X 15"	EACH	6		6			
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	4		4			
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	118		118			
542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	216		216			
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	76		76			
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	68		68			
542D0015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	54		54			
542D0036	PIPE CULVERTS, CLASS D, TYPE 1 36" (TEMPORARY)	FOOT	26		26			
54213450	END SECTIONS 15"	EACH	4		4			
54213459	END SECTIONS 24"	EACH	2		2			
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	8		8			
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1		1			
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1		1			
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1		1			
54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS EQUIVALENT ROUND-SIZE 30"	EACH	4		4			
54215967	REINFORCED CONCRETE PIPE ELBOW 12"	EACH	4	4				
54216231	REINFORCED CONCRETE PIPE TEE, 42" PIPE WITH 12" RISER	EACH	2		2			
54216597	REINFORCED CONCRETE PIPE TEE, 36" PIPE WITH 15" RISER	EACH	1		1			
54218451	REINFORCED CONCRETE PIPE TEE, 42" PIPE WITH 36" RISER	EACH	1		1			
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	1		1			
54248150	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 30"	EACH	4		4			
54248510	CONCRETE COLLAR	CU YD	1.6		1.6			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1310	927	383			
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	244		244			
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	254		254			
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	26		26			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	317	159	158			
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	188		188			
550A0940	STORM SEWERS, CLASS A, TYPE 4 12"	FOOT	52	52				
55100500	STORM SEWER REMOVAL 12"	FOOT	722	612	110			
55100700	STORM SEWER REMOVAL 15"	FOOT	629		629			
55100900	STORM SEWER REMOVAL 18"	FOOT	95		95			
55101800	STORM SEWER REMOVAL 42"	FOOT	40		40			

* SPECIALTY ITEM