

# SUMMARY OF QUANTITIES

F.A. R.T.E. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
899	1-1	ROCK ISLAND	899	8
STA. 75+60.93		TO STA. 116+00.00		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT # 84986				

← URBAN →

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITIES	2 - LANE 75+61 - 86+07		4 - LANE 86+07 - 116+00		90% STATE 10% CITY Y031 - 1F	100% CITY OF ROCK ISLAND Y060	50% STATE 50% CITY SFTY-1B
				100% STATE I000 - 2A	100% STATE I000 - 2A	100% STATE I000 - 2A	100% STATE I000 - 2A			
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	4	2		2				
70100400	TRAFFIC CONTROL AND PROTECTION, STANDARD 701431	EACH	4	2		2				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.2		0.8				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1			1				
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	0.2		0.8				
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	0.2		0.8				
70103810	TRAFFIC CONTROL SURVEILLANCE AND MAINTENANCE	CAL DA	180	45		135				
70300220	TEMPORARY PAVEMENT MARKING LINE 4"	FOOT	15035	4983		10052				
70300280	TEMPORARY PAVEMENT MARKING LINE 24"	FOOT	229			229				
70300520	PAVEMENT MARKING TAPE, TYPE I (I) 4"	FOOT	3046	541		2505				
70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	210	210						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	9973	2745		7228				
72000100	SIGN PANEL - TYPE 1	SQ FT	39.25	15.25		24.00				
72000200	SIGN PANEL - TYPE 2	SQ FT	19.50			19.50				
73000100	WOOD SIGN SUPPORT	FOOT	49	32		17				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	774.8	197.6		577.2				
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15106	4630		10476				
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2530	695		1835				
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	582	205		377				
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	218	45		173				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	311	94		217				
78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4						
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2						
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3546	1269		2277				
80501000	SERVICE INSTALLATION (SPECIAL)	EACH	1				1			
80600100	GROUNDING ELECTRODE IN FOUNDATION	EACH	5				5			
81400200	HEAVY DUTY HANDHOLE	EACH	3				3			
81702110	ELECTRIC CABLE IN CONDUIT, 600 V (XLP-TYPE USE) 1/C NO. 10	FOOT	756				756			
81400300	DOUBLE HANDHOLE	EACH	1				1			
82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTOCCELL CONTROL, 250 WATT	EACH	4				4			
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1				1			
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	567				567			
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	559				559			
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	1263				1263			
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	1224				1224			
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE NO. 6 3C	FOOT	101				101			
87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 15 FT.	EACH	2				2			
87601100	PEDESTRIAN PUSHBUTTON POST, GALVANIZED STEEL, TYPE I	EACH	1				1			
87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT.	EACH	2				2			
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	2				2			
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6				6			
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5				3.5			
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	56.0				56.0			
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	10				10			
89000200	TEMPORARY TRAFFIC SIGNAL INSTALLATION	L SUM	1				1			
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1				1			
89502380	REMOVE EXISTING HANDHOLE	EACH	8				8			
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5				5			

\* SPECIALTY ITEM

# SUMMARY OF QUANTITIES