

# SCHEDULES

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S.B.L. P.A. 224	04-00137-01-FP	HENRY	25	7
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT 05-024199	

STRIP REFLECTIVE CRACK CONTROL TREATMENT			
STATION	FOOT		REMARKS
Wolf Rd.			
L 502+35.76 - 511+87	951	2' WIDE	APPLIED ALONG WIDENING
L 512+14 - 521+58	944	2' WIDE	APPLIED ALONG WIDENING
R 502+35.76 - 521+58	1,922	2' WIDE	APPLIED ALONG WIDENING
Ridge Rd.			
L 10+19 - 12+98	279	2' WIDE	APPLIED ALONG WIDENING
R 10+31 - 12+98	267	2' WIDE	APPLIED ALONG WIDENING
<b>PROJECT TOTAL</b>	<b>4,363</b>		

44300200

BITUMINOUS SHOULDERS SUPERPAVE		
STATION	TON	REMARKS
Wolf Rd.		
L 502+35.76 - 510+74	307	8' & VAR
L 512+78.30 - 522+08.57	284	8', 4' & VAR
R 502+35.76 - 522+08.57	675	8' & VAR
Ridge Rd.		
L 10+19 - 12+12.02	80	8', 4' & VAR
R 10+31 - 12+12.02	51	8', 4' & VAR
<b>PROJECT TOTAL</b>	<b>1,398</b>	

48202000

PIPE CULVERTS, CLASS D, TYPE 1 12"		
STATION	FOOT	REMARKS
L 512+44 - L 513+40	97	
L 513+40 - L 514+50	110	
L 514+50 - L 516+30	180	
L 516+30 - L 518+30	200	
<b>PROJECT TOTAL</b>	<b>587</b>	

542D0217

PIPE CULVERTS, CLASS D, TYPE 1 15"		
STATION	EACH	REMARKS
Wolf Rd.		
PER 505+07	42	
PEL 508+47	32	
HICKORY DR & CER 510+63	90	
FER 512+04	26	
CEL 514+12	38	
PEJ 514+88	32	
PEL 521+15	30	
Ridge Rd.		
PER 11+52	28	
<b>PROJECT TOTAL</b>	<b>318</b>	

542D0220

METAL END SECTIONS 12"		
STATION	EACH	REMARKS
L 518+30	1	
<b>PROJECT TOTAL</b>	<b>1</b>	

54215547

CONCRETE GUTTER, TYPE A (MODIFIED)		
STATION	FOOT	REMARKS
WOLF RD.		
512+44 - 513+92	157	
514+31 - 514+77	46	
515+00 - 518+00	300	
RIDGE RD.		
10+55 - 11+37	84	
<b>PROJECT TOTAL</b>	<b>587</b>	

60602600

CLASS SI CONCRETE (OUTLET)		
STATION	CU YD	REMARKS
L 518+08.87 - 518+45	3	
CE L 514+12	3	
PE L 514+88	2	
<b>PROJECT TOTAL</b>	<b>8</b>	

60600095

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS		
STATION	EACH	REMARKS
Wolf Rd.		
38.56' LT 503+50	1	
45' LT 503+50	1	
45' LT 511+15	1	
45' LT 513+50	1	
45' LT 521+00	1	
39.24' LT 522+00	1	
41.15' RT 506+50	1	
45' RT 506+50	1	
45' RT 513+00	1	
45' RT 520+50	1	
40.73' RT 520+50	1	
Ridge Rd.		
801.8' RT 10+57.10	1	
40' LT 10+91.70	1	
40' LT 12+12.00	1	
27.95' LT 12+12.00	1	
28.81' RT 11+01.29	1	
<b>PROJECT TOTAL</b>	<b>16</b>	

66600105

SHORT-TERM PAVEMENT MARKING		
STATION	FOOT	REMARKS
Wolf Rd.		
L & R 502+35.76 - 522+08.57	350	4-40 CL MARKING - 2 LIFTS
Ridge Rd.		
10+00 - 12+12.02	36	4-40 CL MARKING - 2 LIFTS
<b>PROJECT TOTAL</b>	<b>386</b>	

70300100

WORK ZONE PAVEMENT MARKING REMOVAL		
STATION	SQ FT	REMARKS
Wolf Rd.		
L & R 502+35.76 - 522+08.57	116	
Ridge Rd.		
10+00 - 12+12.02	9	
<b>PROJECT TOTAL</b>	<b>125</b>	

70301000

THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS		
STATION	SQ FT	REMARKS
509+11	21.2	LEFT TURN ARROW
509+91	21.2	LEFT TURN ARROW
510+68	21.2	LEFT TURN ARROW
511+38	21.2	LEFT TURN ARROW
512+97	21.2	LEFT TURN ARROW
513+77	21.2	LEFT TURN ARROW
514+53	21.2	LEFT TURN ARROW
515+33	21.2	LEFT TURN ARROW
<b>PROJECT TOTAL</b>	<b>170</b>	

781000100