

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S.A.L. FA 224	04-00137-01-FP	HENRY	25	8
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT OR ORDER	

SCHEDULES

THERMOPLASTIC PAVEMENT MARKING - LINE 4"		
STATION	FOOT	REMARKS
Wolf Rd.		
L 502+35.76 - 12+12.02	1,578	WHITE EDGE LINE
R 502+35.76 - 522+08.57	1,973	WHITE EDGE LINE
L 12+12.02 - 522+08.57	1,141	WHITE EDGE LINE
503+11 - 511+66	1,712	DBL YELLOW-CL
503+44 - 508+95	1,100	DBL YELLOW-CL
512+41 - 521+34	1,790	DBL YELLOW-CL
512+47 - 520+92	1,700	DBL YELLOW-CL
Ridge Rd.		
10+47 - 12+12.02	41	YELLOW-CL 10-40 SPACING
PROJECT TOTAL	11,035	

78000200

THERMOPLASTIC PAVEMENT MARKING - LINE 8"		
STATION	FOOT	REMARKS
506+34 - 508+92	64	WHITE 3-9 SKIP DASH
508+92 - 511+66	274	WHITE TURN LANE
512+78 - 515+54	276	WHITE TURN LANE
515+54 - 518+09	64	WHITE 3-9 SKIP DASH
PROJECT TOTAL	678	

78000500

THERMOPLASTIC PAVEMENT MARKING - LINE 12"		
STATION	FOOT	REMARKS
503+50 - 508+60	148	YELLOW MEDIAN MARKING
512+75 - 520+49	148	YELLOW MEDIAN MARKING
PROJECT TOTAL	296	

78000600

THERMOPLASTIC PAVEMENT MARKING - LINE 24"		
STATION	FOOT	REMARKS
LT 10+47	25	STOP LINE
PROJECT TOTAL	25	

78000650

RAISED REFLECTIVE PAVEMENT MARKER		
STATION	EACH	REMARKS
Wolf Rd.		
502+30	1	2-WAY AMBER MARKERS
502+70	1	2-WAY AMBER MARKERS
L & R 503+10	2	1-WAY AMBER MARKERS
L & R 503+60	2	1-WAY AMBER MARKERS
L & R 504+00	2	1-WAY AMBER MARKERS
L & R 504+40	2	1-WAY AMBER MARKERS
L & R 504+80	2	1-WAY AMBER MARKERS
L & R 505+20	2	1-WAY AMBER MARKERS
L & R 505+60	2	1-WAY AMBER MARKERS
L & R 506+00	2	1-WAY AMBER MARKERS
L & R 506+40	2	1-WAY AMBER MARKERS
L & R 506+80	2	1-WAY AMBER MARKERS
L & R 507+20	2	1-WAY AMBER MARKERS
L & R 507+60	2	1-WAY AMBER MARKERS
L & R 508+00	2	1-WAY AMBER MARKERS
L 508+40	2	1-WAY AMBER MARKERS
L 508+80	2	1-WAY AMBER MARKERS
R 509+00	1	1-WAY CRYSTAL MARKER
L 509+20	2	2-WAY AMBER MARKERS
R 509+20	1	1-WAY CRYSTAL MARKER
L 509+60	2	2-WAY AMBER MARKERS
R 509+60	1	1-WAY CRYSTAL MARKER
L 510+00	2	2-WAY AMBER MARKERS
R 510+00	1	1-WAY CRYSTAL MARKER
L 510+40	2	2-WAY AMBER MARKERS
R 510+40	1	1-WAY CRYSTAL MARKER
L 510+80	2	2-WAY AMBER MARKERS
R 510+80	1	1-WAY CRYSTAL MARKER
L 511+20	2	2-WAY AMBER MARKERS
R 511+20	1	1-WAY CRYSTAL MARKER
L 511+60	2	2-WAY AMBER MARKERS
R 511+60	1	1-WAY CRYSTAL MARKER
L 512+45	2	1-WAY AMBER MARKERS
L 512+80	1	1-WAY CRYSTAL MARKER
L & R 512+85	2	1-WAY AMBER MARKERS
L 513+20	1	1-WAY CRYSTAL MARKER
L & R 513+25	2	1-WAY AMBER MARKERS
L 513+60	1	1-WAY CRYSTAL MARKER
L & R 513+65	2	1-WAY AMBER MARKERS
L 514+00	1	1-WAY CRYSTAL MARKER
L & R 514+05	2	1-WAY AMBER MARKERS
L 514+80	1	1-WAY CRYSTAL MARKER
L & R 514+45	2	1-WAY AMBER MARKERS
L 515+20	1	1-WAY CRYSTAL MARKER
L & R 514+85	2	1-WAY AMBER MARKERS
L 515+52	1	1-WAY CRYSTAL MARKER
L & R 515+25	2	1-WAY AMBER MARKERS
L & R 515+65	2	1-WAY AMBER MARKERS
L & R 516+05	2	1-WAY AMBER MARKERS
L & R 516+45	2	1-WAY AMBER MARKERS
L & R 516+85	2	1-WAY AMBER MARKERS
L & R 517+25	2	1-WAY AMBER MARKERS
L & R 517+65	2	1-WAY AMBER MARKERS
L & R 518+05	2	1-WAY AMBER MARKERS
L & R 518+45	2	1-WAY AMBER MARKERS
L & R 518+85	2	1-WAY AMBER MARKERS
L & R 519+25	2	1-WAY AMBER MARKERS
L & R 519+65	2	1-WAY AMBER MARKERS

CON'T.

CON'T.

L & R 520+05	2	1-WAY AMBER MARKERS
L & R 520+45	2	1-WAY AMBER MARKERS
L & R 520+85	2	1-WAY AMBER MARKERS
L & R 521+35	2	1-WAY AMBER MARKERS
521+75	1	2-WAY AMBER MARKERS
522+15	1	2-WAY AMBER MARKERS
Ridge Rd.		
L & R 10+50	1	2-WAY AMBER MARKERS
L & R 11+30	1	2-WAY AMBER MARKERS
PROJECT TOTAL	111	

78100100

BREAKER-RUN CRUSHED STONE		
STATION	TONS	REMARKS
CONTINGENCY ITEM	205	AS DIRECTED BY THE ENGINEER
PROJECT TOTAL	205	

Z0005400

INLET SPECIAL WITH FRAME AND GRATE		
STATION	EACH	REMARKS
L 512+44	1	
L 513+40	1	
L 514+50	1	
L 516+30	1	
PROJECT TOTAL	4	